

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22361-00-00
Spot: CSWSWSE Sec/Twnshp/Rge: 3-7S-20W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: PROBASCO Well Number: 1-1
County: ROOKS Total Vertical Depth: 3653 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 1/8.72
Surface Casing: Size 8.625 feet: 332 240 SX CMT
Production: Size 4.5 feet: 3640 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/03/2001 11:30 AM
Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed Plugging Method: According to KCC Rules and Regulations.
Ordered 150 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/03/2001 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 332' w/240 sxs cement.
4 1/2" casing at 3640' w/200 sxs cement.
DV at 1735' w/450 sxs cement.
Tied to 4 1/2" casing - pumped 25 sxs cement - 8 sxs gel - 400# hulls,
followed with 140 sxs cement to Max. P.S.I. 100#. S.I.P. 100#. (bad casing at braden head).
Tied to 8 5/8" annulus, pressure to 200#. Took no cement.
Total of 165 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Remarks: LEASE ALSO KNOWN AS SANDRA K.GOTTSCHALK #1. ALLIED CEMENTING COMPANY. KELLER TANK-

Plugged through: CSG

District: 04

Signed

Roger D. Moses
(TECHNICIAN)

RECEIVED
10/26/01
OCT 26 2001
KCC WICHITA

INVOICED

DATE 10-26-01
INV. NO. 2002060858

Form CP-2/3

OCT 15 2001

DIAMOND SHAMROCK
EXPLORATION COMPANY
P.O. BOX 631
AMARILLO, TX 79173


REPLACEMENT CARD

3-7-20W

#1 SANDRA K. GOTTSCHALK SW SW SE

CONTR MURFIN DRILLING CO. CTY ROOKS

GEOLOGICAL FIELD SLATE SW



ELV 2174 GL SPD 10/27/84 CARD ISSUED 11/8/84 IP P 239 BOPD, NW
DRLG COMP 11/3/84 LKC 3451-3585 OA
API 15-163-22,361

LOG	Tops	Depth/Datum	
TOP		3150-976	8 5/8 " 332 / 240SX, 4 1/2 " 3640 / 200SX, DV TOOL 1735 / 450SX
HEEB		3355-1181	NO CORES
TOR		3380-1206	DST (1) 3384-3423 (LKC) / 30-90-45-135, (1ST OP) BLO OFF
LANS		3397-1223	BTM OF BKT / 4", (2ND OP) SLI BLO, 8 INCH FROM TOP OF BKT
BKC		3598-1424	DECRG TO 4 INCH FROM TOP, REC 1410' CL OIL (GR 31°), 120'
ARB		3646-1472	OCM, SIP 946-930#, FP 49-393 / 408-589#
PBTD		3610-1436	MICT - CO, PF (LKC) 3559-64, W / 2 SPF, AC 1000G (15% MA),
RTD		3653-1479	SWB LD, SO, PF (LKC) 3543-46 & 3582-85, W / SPF, AC 2000G
			(15% NE), SWB LD, SO, PF (LKC) 3489-92, W / 4 SPF, SWB
			DWN, SO, NAT, PF (LKC) 3474-77, W / 4 SPF, AC 3000G (15%
			NE), SWB LD, SO, PF (LKC) 3451-53, SWB DWN, SO, NAT, SET
			2 3/8 " TBG AT 3597', POP, P 239 BOPD, NW, 11/29/84

CORRECTION: 5/16/85 - WAS ABD LOC - EXPIRED PERMIT
NOTE: CORRECTION: 11/8/84 - ORIGINALLY FIRST REPORTED IN SE SW SE

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

33310721

