

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22528-00-00
Spot: CNWSWSE Sec/Twnshp/Rge: 3-7S-20W
990 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: PROBASCO Well Number: 1-2
County: ROOKS Total Vertical Depth: 3652 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 1/8.69
Surface Casing: Size 8.625 feet: 307 200 SX CMT
Production: Size 4.5 feet: 3640 500 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/03/2001 2:00 PM

Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC

Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 150 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL
Date/Time Plugging Completed: 10/03/2001 3:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 307' w/200 sxs cement.
4 1/2" casing at 3640' w/unknown cement.
DV at 1738' w/500 sxs cement.
Tied to 4 1/2" casing - pumped 25 sxs cement - 8 sxs gel - 400# hulls,
followed with 135 sxs cement to Max. P.S.I. 500#. S.I.P. 200#.
Tied to 8 5/8" annulus - took 10 sxs cement to Max. P.S.I. 350#. S.I.P. 0#.
Total of 170 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Remarks: LEASE ALSO KNOWN AS SANDRA K.GOTTSCHALK #1. ALLIED CEMENTING COMPANY. KELLER TANK-

Plugged through: CSG

District: 04

RECEIVED
OCT 26 2001
KCC WICHITA

Signed

Roger L. Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 10-26-01

INV. NO. 2002060858

OCT 15 2001

DIAMOND SHAMROCK
EXPLORATION COMPANY
P.O. BOX 400

#1 SANDRA K. GOTTSCHALK

3-7-20W
NW SW SE


AMARILLO, TX 79188-0001

CONTR MURFIN DRILLING

CTY ROOKS

GEOLOGICAL HAL CLARK

FIELD PROBASCO



ELV 2176 KB SPD 10/31/84 CARD ISSUED 3/28/85 IP P 57 B0 & 49 BWPD
2177 GL DRLG COMP 11/6/84 LKC 3450-3588 OA

LOG	Top	Depth/Datum	
			8 5/8 " 307/200SX, 4 1/2 " 3640/500SX NO CORES
ANH	1733 + 443	DST (1) 3386-3425 (LKC) / 30-90-30-90, (1ST OP) FB BLDG TO 10.5 INCH IN TO BKT THRU-OUT, (2ND OP) FB BLDG TO 6 INCH INTO BKT, REC 20' CL OIL, 90' G&OCMW, 120' MW (SMPL REC 200 CC OIL, 1600 CC W AT 100 PSI), SIP 929-929#, FP 49-89 / 109-128#
HEEB	3358-1182	
TOR	3380-1204	
LANS	3386-1210	DST (2) 3443-75 (LKC) / 30-90-30-90, (1ST OP) WB INCRG TO 3 INCH IN BKT, (2ND OP) WB INCRG TO 3 INCH IN BKT, REC 20' CL OIL, 60' OCM, SIP 948-899#, FP 39-39 / 59-59#
BKC	3599-1423	
ARB	3640-1464	
PBTD	3615-1439	MICT - CO, PF (LKC) 3584-88, 3562-66, 3546-52, 3488-92, 3476-82, 3470-75, 3450-53, AC 2000G (15% EMUL) & 3000G (20% NON-EMUL), SWB DWN, GSO, SET 2 3/8 " TRBG AT, 3597', POP, P 57 B0 & 49 BWP, 12/1/84
RTD	3652-1476	

NOTE: CORRECTION 11/6/84 - ORIGINALLY FIRST REPORTED AS #2 SANDRA K. GOTTSCHALK

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

3301078