

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22553-00-00  
Spot: CNESWSE Sec/Twnshp/Rge: 3-7S-20W  
990 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: PROBASCO Well Number: 1-3  
County: ROOKS Total Vertical Depth: 3645 feet

Operator License No.: 5011  
Op Name: VIKING RESOURCES, INC  
Address: 105 S BROADWAY, STE 1040  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 304 200 SX CMT *3118.46*  
Production: Size 4.5 feet: 3628 200 SX CMT  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/03/2001 8:00 AM  
Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC  
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 150 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/03/2001 10:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 304' w/200 sxs cement.  
4 1/2" casing at 3628' w/200 sxs cement.  
DV at 1735' w/525 sxs cement.  
Tied to 4 1/2" casing - pumped 25 sxs cement - 8 sxs gel with 400# hulls,  
followed with 100 sxs cement to Max. P.S.I. 150#. Casing at braden head popped. S.I.P. 0#.  
Tied to 8 5/8" S.P. - pressured to 800#. No Cement.  
Total 125 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Remarks: LEASE ALSO KNOWN AS SANDRA K.GOTTSCHALK #3. ALLIED CEMENTING COMPANY. KELLER TANK-

Plugged through: CSG

District: 04

Signed

Roger L. Moses  
(TECHNICIAN)

RECEIVED

OCT 26 2001

KCC WICHITA

OCT 15 2001

INVOICED

Form CP-2/3

DATE 10-26-01

INV. NO. 2002060858

DIAMOND SHAMROCK  
EXPLORATION COMPANY  
P.O. BOX 400


#3 SANDRA K. GOTTSCHALK

3-7-20W  
NE SW SE

AMARILLO, TX 79188-0001

CONTR BIG SPRINGS DRILLING CTY ROCKS

GEOL MICHEL L. RUSSELL FIELD SLATE SW



ELV 2175 KB SPD 11/16/84 CARD ISSUED 4/18/85 IP P 130 BO & 70 BWPD  
2170 GL DRLG COMP 11/23/84 LKC 3388-3583 OA

LOG	Tops	Depth/Datum	API 15-163-22.553
ANH	.....	1734+ 441	8 5/8 " 304 / 200SX, 4 1/2 " 3628 / 200SX, DV TOOL AT 1735 / 525SX
TOP	.....	3148- 973	NO CORES
HEEB	.....	3352-1177	DST (1) 3382-3422 (TOR, LANS) / 30-60-15-30, REC 30' OCM (10% OIL, 90% M), SIP 968-952#, FP 34-34 / 34-40#
TOR	.....	3375-1200	DST (2) 3432-84 (LKC) / 30-60-30-60, REC 2' CL OIL, 120' OCM (20-25% OIL), SIP 796-796#, FP 61-77 / 86-102#
LANS	.....	3391-1216	DST (3) 3524-97 (LKC) / 30-60-30-60, REC 205' WM, 255' MM, SIP 1299-970#, FP 318-397 / 322-420#
BKC	.....	3595-1420	DST (4) 3616-45 (PENN, ARB) / 30-60-15-30, REC 20' DM, W / OIL SPKS, SIP 954-571#, FP 27-37 / 37-37#
ARB	.....	3633-1458	MIC - CO, PF (LKC) 3578-83, 3551-60 & 3538-43, W / 4 SPF, AC 3000G (15% NON-EMUL), SWB LD, SO, PF (LKC) 3516-20, W / 4 SPF, AC 750G (15% NON-EMUL), SWB LD, SO, PF (LKC) 3470-76, 3463-65, & 3455-58, W / 4 SPF, AC 1500G (15% NON-EMUL), SWB LD, SO, PF (LKC) 3430-34 & 3388-91, W / 4 SPF, AC 1000G (15% MCA), SWB LD, SO, SET 2 3/8 " TBG AT 3614, POP, P 130 BO & 70 BWPD, 12/27/84, (GR 33°)
RTD	.....	3645-1470	

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS