

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22755-00-00
Spot: CSWNWSE Sec/Twnshp/Rge: 3-7S-20W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: PROBASCO Well Number: 1-6
County: ROOKS Total Vertical Depth: 3650 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet: 318.63
Surface Casing: Size 8.625 feet: 308 250 SX CMT
Production: Size 4.5 feet: 3649 725 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/03/2001 12:30 PM

Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC

Proposal Rcvd. from: SHAWN P. DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 150 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/03/2001 1:30 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 308' w/250 sxs cement.
4 1/2" casing at 3649' w/200 sxs cement.
DV at 1776' w/525 sxs cement.
Tied to 4 1/2" casing - pumped 25 sxs cement with 8 sxs gel and 400# hulls,
followed with 100 sxs cement to Max. P.S.I. 800#. S.I.P. 800#.
Tied to 8 5/8" annulus and pressured to 500#. No cement.
Total of 125 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Remarks: LEASE ALSO KNOWN AS SANDRA K.GOTTSCHALK #6. ALLIED CEMENTING COMPANY. KELLER TANK-

Plugged through: CSG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

RECEIVED

OCT 26 2001

OCT 15 2001

KCC WICHITA

INVOICED

DATE 10-26-01

INV. NO. 2002060858

DIAMOND SHAMROCK
EXPLORATION COMPANY
P.O. BOX 400

REPLACEMENT CARD

#6 SANDRA K. GOTTSCHALK

3-7-20W
SW NW SE

AMARILLO, TX 79188-0001

CONTR ABERCROMBIE DRILLING


CTY

ROOKS

GEOL DOUG DAVIS

FIELD

PROBASCO



ELV 2183 KB SPD 9/24/85 CARD ISSUED 11/21/85 IP P 20 BO & 28 BWPD
2178 GL DRLG COMP 10/2/85 LKC 3556-3580 OA
API 15-163-22,755 ARB 3594-3606 OA

LOG	Tops	Depth/Datum
ANH	1744+ 439
HEEB	3366-1183
TOR	3388-1205
LANS	3402-1219
BKC	3472-1289
ARB	3592-1409
RTD	3650-1467

8 5/8 " 308 / 250SX, 4 1/2 " 3649 / 725SX
DST (1) 3546-68 (LKC) / MISRUN
DST (2) 3572-84 (LKC) / MISRUN
DST (3) 3516-86 (LKC) / 30-60-30-60, REC 2200 CC MUD, SO,
SIP 1108-995#, FP 616-731#
MICT - CO, PF (ARB) 3604-06, W / 4 SPF, AC 1000G (15% NE),
SWB DWN, SO, PF (ARB) 3594-3602, W / 4 SPF, AC 1000G (15%
NE), SWB DWN, SO, PF (LKC) 3572-80, W / 4 SPF, AC 2000G
(GEL AC), SWB DWN, SO, PF (LKC) 3556-61, W / 4 SPF, AC
2000G (15% NE), SWB DWN, SO, SET 2 3/8 " TBG AT 3594',
POP, P 20 BO & 28 BWPD (GR 60°), COMMINGLED, 10/8/85

INFO RELEASED: 12/5/85 - ADDED WELL INFO