

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22766-00-00
Spot: CNENWSE Sec/Twnshp/Rge: 3-7S-20W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: PROBASCO Well Number: 1-7
County: ROOKS Total Vertical Depth: 3615 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size _____ feet: _____
Surface Casing: Size 8.625 feet: 319 250 SX CMT **8/17.49**
Production: Size 4.5 feet: 3614 250 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2001 10:30 AM
Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 150 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/03/2001 12:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 319' w/250 sxs cement.
4 1/2" casing at 3614' w/250 sxs cement.
DV at 1710' w/475 sxs cement.
Tied to 4 1/2" casing - pumped 25 sxs cement - 8 sxs gel with 400# hulls,
pumped 100 sxs cement to Max. P.S.I. 800#. S.I.P. 500#.
8 5/8" annulus to 500#. No cement.
Total 125 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Remarks: LEASE ALSO KNOWN AS SANDRA K.GOTTSCHALK #7. ALLIED CEMENTING COMPANY. KELLER TANK-

Plugged through: CSG

District: 04

Signed

Roger D. Moses
(TECHNICIAN)

RECEIVED

OCT 26 2001

KCC WICHITA

OCT 15 2001

INVOICED

DATE 10-26-01

INV. NO. 2002060858

Form CP-2/3

DIAMOND SHAMROCK
EXPLORATION COMPANY
P.O. BOX 400


#7 SANDRA K. GOTTSCHALK 3-7-20W
NE NW SE

AMARILLO, TX 79188-0001

CONTR ABERCROMBIE DRILLING CTY ROOKS

GEOL _____ FIELD PROBASCO

ELV 2146 KB SPD 10/2/85 CARD ISSUED 11/21/85 IP P 42 BOPD, NW
2141 GL LKC 3506-3526



LOG	Tops	Depth/Datum	API 15-163-22,766
HEEB	3323-1177	8 5/8 " 319 / 250SX, 4 1/2 " 3614
TOR	3345-1199	DST (1) 3386-3441 (LKC) / 30-60-30-90, REC 280' CL OIL, 155'
LANS	3360-1214	MCO, SIP 1049-997#, FP 72-185#
ARB	3602-1456	MIC - CO, PF (LKC) 3506-26, W / 2 SPF, AC 1000G (15% MCA),
RTD	3615-1469	SWB DWN, SO, POP, P 42 BOPD, NW, 11/1/85

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS