

12-30

4-041650

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-22,228 <sup>0000</sup>

SE NE SE /4 SEC. 03 , 07 S , 20 W  
1650 feet from S section line  
330 feet from E section line

Operator license# 5011

Lease Gottschalk "B" well # 1

Operator: Viking Resources, Inc.

County Rooks

Address: 105 S. Broadway  
Suite #1040  
Wichita, Kansas 67202

Well total depth 3670 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 266 feet  
w/200 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing. License#    

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 30 Month: December Year: 94

Plugging proposal received from: Terry Richardson

Company: Viking Resources, Inc. Phone:    

Were: 4 1/2" casing set @ 3668' w/175 sxs. cmt. Perf. @ 3532' - 3538'.  
Salt @ 2000' - Anhy. @ 1725' - Dakota @ 1000' - W.L.M. @ 3600' -  
T.O.F. @ 1700'.

Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel - Herb Deines  
Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 12:00P.M., Day: 30, Month: December, Year: 94

Actual plugging report: Perf. casing - hooked-up to 4 1/2" casing and  
squeezed 250 sxs. 60/40 pozmix - 10% gel w/400# hulls. Max. P.S.I. 500#.  
S.I.P. 300#. Hooked-up to 8 5/8" S.P. - Squeezed 50 sxs. cement  
w/100# hulls. Max. P.S.I. 300#.

Remarks:      
Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:    

I did X / did not     observe the plugging.

*Dennis J. Hamel*  
HD

(agent)

JAN 17 1995

Form CP-2/3 STATE CORPORATION COMMISSION  
WICHITA, KANSAS 67202

INVOICED

DATE 1-18-95

INV. NO. 40271

MAR 16 1995