

10-28-87

6 030988

API NUMBER 15- 163-22,577-6000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SE SE, SEC. 3, T 7 S, R 20 W/E  
990 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6278

Lease Name Gottschalk Well # 1-C

Operator: - Petx Petro, Corp -  
Name & Address: Sunrise OilField Supply Co.  
104 S. Broadway #1400  
Wichita, Kansas 67202

County Rooks 119.93  
Well Total Depth 3690 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing Co. License Number \_\_\_\_\_

Address Russell, Kansas

Company to plug at: Hour: AM Day: 28 Month: October Year: 19 87

Plugging proposal received from Mike Lovelady

(company name) Sunrise (phone) \_\_\_\_\_

were: 8 5/8" set at 258' w/160 sks cwc 5 1/2" set at 3689' w/125 sks. Perfs at 3374' -  
3620'. Perf at 1700' and shot off at 1035' and pulled pipe. Order sand and Common  
Cement. Pull pipe. Order 200 sks ATL 65/35 Pozmix 10% Gel 2% Dical Cement Blend.  
5 sks Hulls. Allied Cement Co. OWS Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15 AM Day: 28 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3324' w/5 sks Common Cement on sand w/bailer.

Shot at 1700' Anhy and 1035' (Below Dakota) w/1035' of recovery. Squeezed 8 5/8"  
casing w/200 sks ATL Cement Blend w/5 sks Hulls mixed in. Max Psi 1200#. Close in  
PSI 300#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 18 1987

11/18/87  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: (If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 12-3-87

INV. NO. 19064

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow