

4-041651

12-30

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-22754-0000

NW NW SE /4 SEC. 03, 07 S, 20 W
2310 feet from S section line
2310 feet from E section line

Operator license# 5011 Lease Probasco well # 1-5

Operator: Viking Resources, Inc. County Rooks

Address: 105 S. Broadway Well total depth 3650 feet ^{118.63}
Suite #1040 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 307 feet
w/250 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 30 Month: December Year: 94

Plugging proposal received from: Terry Richardson

Company: Viking Resources, Inc. Phone:

Were: 4 1/2" casing set @ 3649' w/200 sx. cement. Perf. at 3560' - 3587'. W.L.M. at 3585' - T.O.F. at 2000' - D.V. at 1762' - C.W. - 400 sx. cement.

Ordered 200 sx. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Herb Deines - Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 4:00P.M., Day: 30, Month: December, Year: 94

Actual plugging report: Squeezed down 4 1/2" casing - 175 sx. 60/40 pozmix - 10% gel with 300# hulls in cement. Max. P.S.I. 500#. S.I.P. 500#. 8 5/8" S.P. - cement at surface with 10 sx. and 500# S.I.

RECEIVED
KANSAS CORPORATION COMMISSION
11/30/95
JAN 30 1995

Remarks: CONSERVATION DIVISION
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO WICHITA, KS
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did not observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 2-1-95

INV. NO. 42119

12-30 MAR 16 1995