

6 070506

56R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-~~113~~-228110000

SW-SE-NE, SEC. 2, T 7 S, R 20 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 8000

Lease Name G.L. States Well # 42-3

Operator: Panconadian Petroleum Co.

County Rooks 121.06

Name & Address P.O. Box 929

Well Total Depth 3725 feet

Denver, Colo. 80201

Conductor Pipe: Size 0 feet

J.D. Keisling.

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B.J. Titan License Number \_\_\_\_\_

Address Hays, Kans 67601

Company to plug at: Hour: 1:00 PM Day: 5<sup>th</sup> Month: Sept Year: 1986

Plugging proposal received from Tom Pufis

(company name) Panconadian Petroleum Co (phone) 303-825-8271

were: 8 5/8" @ 293<sup>ft</sup> SR. #/215<sup>ft</sup> cmt, ccl #/ 4 1/2" csg set @ 3723<sup>ft</sup> #/205<sup>ft</sup> cmt.

D.V. Tool @ 1736<sup>ft</sup> ccl #/395<sup>ft</sup> cmt, PBTD 3680<sup>ft</sup>, Perf 3550<sup>ft</sup>.

To 3568<sup>ft</sup>, No Pipe Recovery, Proposal, ordered 125<sup>SK</sup> Cement,

65% Pozmix 10.9% Gel-Additive, 2% #/ 6<sup>SK</sup> shells, with pump truck, load and pressure

Annulus #/cement, shut in under pressure, load and pressure 4 1/2" csg with

Cement. #/shut in under pressure. Plugging Proposal Received by M. Schmidt

Plugging Operations attended by Agent? All  Part  None

Operations Completed: Hour: 3:00 PM Day: 5<sup>th</sup> Month: Sept Year: 1986

ACTUAL PLUGGING REPORT Ordered 125<sup>SK</sup> Cordlife a thrifty mix

65% Pozmix 10% Gel-Additive, and 5<sup>SK</sup> shells

Pumped in Annulus 10<sup>SK</sup> Cement, 500<sup>PSI.g.</sup> (with pump truck)

Pumped in 4 1/2" csg, 10<sup>SK</sup> cmt 4<sup>SK</sup> shells and

125<sup>SK</sup> Cement #/ 1<sup>SK</sup> shells mixed in. Max. Pressure.

800 PSI.g., Cemented by B.J. Titan. Hays.

Remarks: of additional description is necessary, use BACK of this form.)

INVOICED

I (did/did not) observe this plugging.

DATE 9-17-86

Signed M. Schmidt (TECHNICIAN)

INV. NO. 14961

9/15/86