

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23296-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 34-11S-13W
2210 feet from N Section Line, 330 feet from W Section Line
Lease Name: CRAWFORD Well #: 1-34
County: RUSSELL Total Vertical Depth: 3133 feet

Operator License No.: 30129
Op Name: EAGLE CREEK CORPORATION
Address: 150 N. MAIN, STE 905
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	454		

#10182

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/24/2005 10:20 AM
Plug Co. License No.: 5892 Plug Co. Name: BERENTZ DRILLING CO., INC.
Proposal Rcvd. from: DAVE COLLAERT Company: EAGLE CREEK CORPORATION Phone: (316) 264-8044

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 08/25/2005 10:30 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st. Plug at 830' w/25 sxs.
2nd. Plug at 530' w/100 sxs.
3rd. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: ACID SERVICES, INC.

Plugged through: DP

District: 04

Signed

Ed Schumacher

(TECHNICIAN)

INVOICED

DATE

8-29-05

REF. NO.

2006060396

RECEIVED

AUG 29 2005

KCC WICHITA

Form CP-2/3

AUG 25 2005