

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-19288-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 26-33S-11E
1810 feet from S Section Line, 2475 feet from E Section Line
Lease Name: GARDNER Well #: 2
County: CHAUTAUQUA Total Vertical Depth: 1150 feet

Operator License No.: 7644
Op Name: MILLER, BOBBY ELZO
Address: 2061 INDEPENDENCE RD, UNIT 23
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	1100		
SURF	10	40		

237 38

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/15/2005 8:00 AM

Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.

Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed TO PUMP GEL & CEMENT FOR BOTTOM & TOP PLUGS.
Plugging Method:

Plugging Proposal Received By: RON ROWE

Witness Type: NONE

Date/Time Plugging Completed: 07/19/2005 5:00 PM

KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" HYDRIL WORK-STRING TUBING INSIDE 7" CASING TO 1100' & GELLED HOLE, THEN PUMPED 20 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" UP TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE, INSIDE & OUTSIDE 7" CASING. PULLED 1" & TOPPED-OFF WELL. USED TOTAL OF 218 SACKS CEMENT & 6 SACKS GEL.

Perfs:

RECEIVED
KCC DISTRICT #3

AUG 15 2005 *RR*

CHANUTE, KS

Remarks: PLUGGED OLD OIL WELL.

Plugged through: TBG

District: 03

Signed *John B. Sauer*

(TECHNICIAN)

INVOICED
DATE 8-26-05
WV. NO. 2006010080

RECEIVED
AUG 26 2005 *RR*
KCC WICHITA