

3 022803

To:

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER

N/A

15 001-01979-0000

NE,NE,NE 1/4

Sec/Twp/Rge

S.19-T.26S.-R.19E.

5115 feet from south section line

495 feet from east section line

\$ 35.00

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

WHITAKER NO.3

Operator License #

6554

County

ALLEN

Operator: HAROLD DEAN WHITAKER

Well Total Depth

900'

feet

Name & 266-2000ST

Production Pipe: 2"

Size Feet 900'

Address HUMBOLDT, KANSAS 66748

Surface Casing: 6 1/4"

Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: W&W PRODUCTION CO.

Lic. #

5491

Address: 1150 HWY 39, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:20A.M. Day: 22 Month: 7 2005

Plugging proposal received from: MIKE WIMSETT

Company Name: W&W PRODUCTION CO.

Phone:

620-431-4137

Were: THIS WELL CONSISTED OF 2 " CASING TO APPROXIMATELY 900'

THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL

WAS TO SQUEEZE THE 2 " CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

☒

Part

TECHNICIAN

None

Operations Completed: Hour:

11:10A.M. Day:

22 Month:

7

2005

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE

2 " CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO

BE PUMPED. CEMENT WAS PUMPED INTO THE 2 " CASING UNTIL THE WELL WOULD

HOLD PRESSURE THE WELL WAS THEN SHUT IN AT 400 PSI. 28 SACKS OF CEMENT WERE

PUMPED INTO THIS WELL.

Remarks:

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED

AUG 12 2005

KCC WICHITA

INVOICED

DATE

8-26-05

INV. NO.

2006060389

Signed

Clayton P. Titel  
TECHNICIAN