

3 022801

To:

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER N/A 15-001-01977-00 00  
NW,NE,NE 1/4 Sec/Twp/Rge S.19-T.26S.-R.19E.  
5115 feet from south section line  
1155 feet from east section line \$35<sup>00</sup>

TECHNICIAN'S PLUGGING REPORT

Operator License # 6554

Lease/Well# WHITAKER NO.1

County ALLEN

Operator: HAROLD DEAN WHITAKER

Well Total Depth 900' feet

Name & 266-2000ST

Production Pipe: 2 1/2" Size Feet 900'

Address HUMBOLDT, KANSAS 66748

Surface Casing: 7" Size Feet 20'

AB oil well X Gas Well        SWD Well/ Input Well       

D & A       

Other well as hereinafter indicated:       

Plugging Contractor: W&W PRODUCTION CO.

Lic. # 5491

Address: 1150 HWY 39, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:00A.M. Day:        22 Month:        7 2005

Plugging proposal received from: MIKE WIMSETT

Company Name: W&W PRODUCTION CO.

Phone: 620-431-4137

Were: THIS WELL CONSISTED OF 2 1/2" CASING TO APPROXIMATELY 900'

THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL

WAS TO SQUEEZE THE 2 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All X Part       

TECHNICIAN  
None       

Operations Completed: Hour: 9:45A.M. Day:        22 Month:        7 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE

2 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO

BE PUMPED. CEMENT WAS PUMPED INTO THE 2 1/2" CASING UNTIL THE WELL WOULD

HOLD PRESSURE THE WELL WAS THEN SHUT IN AT 800 PSI. 30 SACKS OF CEMENT WERE

PUMPED INTO THIS WELL.

Remarks:

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

RECEIVED

AUG 12 2005

KCC WICHITA

INVOICED

DATE

8-26-05

INV. NO.

2006060389