

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

RECEIVED
AUG 08 2005
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
Initials must be Filled

Lease Operator: John O. Farmer, Inc.
 Address: P.O. Box 352, Russell, KS 67665
 Phone: (785) 483-3144 Operator License #: 5135
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: District #4 (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2878' Bottom: _____ T.D. _____
Lansing Depth to Top: 3185' Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. 3420'

API Number: 15 - 163-1911-00-00 (Completed 7/17/40)
 Lease Name: Luhman Johnson
 Well Number: #1
 Spot Location (QQQQ): _____ - S/2 - SE - NW
2310 Feet from North / South Section Line
1980 Feet from East / West Section Line
 Sec. 10 Twp. 9S S. R. 16 East West
 County: Rooks
 Date Well Completed: 7-17-40
 Plugging Commenced: 9:15 A.M., 7-1-05
 Plugging Completed: 11:15 A.M., 7-1-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	oil & water			7"		-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 342 sks. cement; plugged w/2" tubing - 450# hulls; shut in @ 250 PSIG. Mixed 108 sks. cement down backside w/150# hulls.
Shut in @ 150 PSIG. THERE WAS LIMITED INFORMATION AVAILABLE TO PLUG THIS OLD WELL.
OUR PUMPER, JEFF CRAWFORD, WORKED IN CONJUNCTION WITH PAT STAAB AT THE DISTRICT #4 OFFICE
TO COMPLETE THIS PLUGGING ON WHAT WAS ORIGINALLY CONSIDERED THE T.C. JOHNSON LUHMAN #1 WELL.

Name of Plugging Contractor: Allied Cementing Company, Inc. John Farmer License #: 5135
 Address: R.O. Box 31, Russell, KS 67665

*KCC
8-9-05
BEM
RBDMS
CP 2/3*


Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.
 State of Kansas County, Russell, ss.

John O. Farmer IV (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John O. Farmer IV
 (Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 5th day of August, 20 05

Margaret A. Schulte My Commission Expires: _____
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm

RECEIVED

ALLIED CEMENTING CO., INC.

21536

Federal Tax I.D.#

WICHITA

REMIT TO P.O. BOX 31 RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>7/1/05</u>	SEC.	TWP.	RANGE	CALLED OUT <u>7:00 am</u>	ON LOCATION <u>9:00 am</u>	JOB START <u>9:15 am</u>	JOB FINISH <u>11:15 am</u>
LEASE <u>Lubhay Johnson</u>	WELL # <u>1</u>	LOCATION <u>Natoma 4w 6 1/2 N</u>		COUNTY <u>Rooks</u>	STATE <u>Ks</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>1/2 E Sinto</u>			

COPY

CONTRACTOR _____ OWNER _____

TYPE OF JOB Old Hole Plug

HOLE SIZE _____ T.D. _____

CASING SIZE 7" DEPTH _____

TUBING SIZE 2' DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 1000 psi MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT	AMOUNT ORDERED	<u>450 @ 10.96</u>	<u>109.60</u>
	<u>600 # Halls</u>		
COMMON	<u>270</u>	@ <u>8.70</u>	<u>2,349.00</u>
POZMIX	<u>180</u>	@ <u>4.70</u>	<u>846.00</u>
GEL	<u>31</u>	@ <u>14.00</u>	<u>434.00</u>
CHLORIDE		@	
ASC		@	
	<u>Halls 6</u>	@ <u>21.00</u>	<u>126.00</u>
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>4.87</u>	@ <u>1.60</u>	<u>779.20</u>
MILEAGE	<u>6 d/sk/mile</u>		<u>1,051.92</u>
TOTAL			<u>5,586.12</u>

EQUIPMENT

PUMP TRUCK CEMENTER Shane

366 HELPER Fred

BULK TRUCK _____

362 DRIVER Gary

BULK TRUCK _____

213 DRIVER Aug

REMARKS:

Mixed 342 sks down 2' with
450 # Halls shut in @ 250 psi.
Mixed 108 sks down backside
with 150 # Halls shut in @
150 psi

CHARGE TO: John O' Farmer

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>600.00</u>
EXTRA FOOTAGE	@		
MILEAGE	<u>36</u>	@ <u>5.00</u>	<u>180.00</u>
MANIFOLD	@		
	@		
	@		
TOTAL			<u>780.00</u>

PLUG & FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		
TOTAL			_____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

Thanks
Jeff Crawford

SIGNATURE _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____