

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-22,139-00-00

LEASE NAME Wills

WELL NUMBER #2

2,310 Ft. from S Section Line

990' Ft. from E Section Line

SEC. 2 TWP. 7 RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 3-3-84 *9-22-83 KCC*

Plugging Commenced 5-8-90

Plugging Completed 5-8-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS Box 8647 Wichita, Ks. 67208

PHONE# (316) 681-0231 OPERATORS LICENSE NO. 8061

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-8-90 (date)

by Gilbert Balthazon (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? Yes

Producing Formation Lansing-Ks City Depth to Top 3,367'-3,372' Bottom T.D. 3,670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
<u>Arbuckle</u>	<u>oil, water</u>	<u>3,609'</u>	<u>3,670'</u>	<u>8 5/8"</u>	<u>251'</u>	<u>None</u>
<u>Lansing-Ks City</u>	<u>oil, water</u>	<u>3,366'</u>	<u>3,370'</u>	<u>4 1/2"</u>	<u>3,669'</u>	<u>None</u>

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 15 1990
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Fluid level in the casing at 2,900' from the surface. Pumped 10 sacks 60-40 Pozmix cement, 8% gel down the casing annulus at 500 psi and held. Pumped 200 sacks of 60-40 Pozmix, 8% gel down the 4 1/2" casing. Pressure increased to 1,000 psi and held. Shut-in valves on the annulus and casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing, Inc. License No. _____

Address Plainville, Ks. 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas Box 8647 Wichita, Ks. 67208

STATE OF Kansas COUNTY OF Russell, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) James R. Lane

(Address) 29 Ober St. Russell, Ks. 67665

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 90

Lauraine Weathers
 Notary Public

My Commission Expires: January 29, 1993


15-163-22139-00-00

WELL LOG

COMPANY OIL PRODUCERS, INC. OF KS
 P.O. Box 8647
 Wichita, KS 67205
 FARM WILLS NO 2

SEC. 2 T. 7S R. 20W
 LOG. 990' FEL 2310' FSL

RIG. NO. 15
 TOTAL DEPTH 3670'
 COMM. 9-17-83 COMP. 9-22-83




CONTRACTOR MURFIN DRILLING COMPANY
 250 N. Water, Suite 300
 Wichita, KS 67202

CASING TO 10
 15 5/8" csg set @ 251' w/150 sx. Quickset ELEVATION
 12 6
 13 4 1/2" csg set @ 3669' w/525 sx. 1st Stage: 150 sx. Common, 10% salt. PRODUCTION
FIGURES INDICATE BOTTOM OF FORMATIONS
 2nd stage: 375 sx. 50-50 Pox., 6% gel

- Shale & Sand 1207'
- Sand (Cedar Hills) 1431'
- Shale 1703'
- Anhydrite 1735'
- Shale 2265'
- Shale & Lime 3615'
- Lime & Arb. (RTD) 3670'

State of KANSAS
 County of SEDGWICK) ss:

I, David L. Murfin of the Murfin Drilling Company
 upon certificate that the above and foregoing is a true and correct copy of the log of the WILLS #2 well.



David L. Murfin
 David L. Murfin
 My Comm. Expires on this 5th day of October 1983
Eleanore Hall
 Eleanore Hall NOTARY PUBLIC

RECEIVED
 STATE CORPORATION COMMISSION

MAY 15 1990
 MAY 15, 1990
 CONSERVATION DIVISION
 Wichita, Kansas