

APR 23 1982

CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

15-179-05156-00-01

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Sheridan County, Sec. 12 Twp. 6 Rge. 27 (X) (W)
Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner Conoco, Inc.
Lease Name Adell LKC WFU (Formerly J E Leonard) #6 Well No. 206
Office Address Box 267 Great Bend, KS
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed as oil well 11-5-47 - disposal well 5-10-49
Application for plugging filed 12-23 1981
Application for plugging approved 1-11- 1982
Plugging commenced 8:00 AM February 26, 1982
Plugging completed 10:57 AM March 17, 1982
Reason for abandonment of well or producing formation Casing Bad
No Longer Can Be Used for Salt Water Disposal
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt, Carl Goodrow, Frank Broadfoot
Producing formation Lansing Kansas City. Depth to top 3579 Bottom 3784 Total Depth of Well 4023
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Quartzite	Used for SWD	4002	4022	10 3/4 OD	300	0
				6 OD	3874	0
				4 1/2 OD	221	0
				2 7/8 OD	1500	0
				2 7/8 OD	205	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Milled & Clean Out To 206 Ft. Unable To Clean Out Any Deeper. Ran 205 Ft. 2 7/8 TBG And Circulated 90 Sacks Cement From 200 Ft To Surface. Let Cement Plug Set Up. Then Squeezed Down 2 7/8 TBG And Surface Casing Four Feet Below Ground Level. Leveled Location.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Conoco, Inc., Plainville Well Service, Acme Tool Co. & Halliburton Oil Cementing
Address Box 267 Great Bend, KS 67530

STATE OF Oklahoma COUNTY OF Oklahoma ss.
Conoco, Inc. (XXXXXXXXXXXX)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dillon Anders Adm. Supervisor
3535 N.W. 58th Oklahoma City, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of April 1982

My commission expires

June 23, 1984

Beverly G. Hatters
Notary Public.