

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-179-05517-00-00

API NUMBER 6-18-62 (compl.)

LEASE NAME Ade11 LKC

WELL NUMBER 210

5180 Ft. from S Section Line

4730 Ft. from E Section Line

SEC. 12 TWP. 6S RGE. 27 (W)

COUNTY Sheridan

Date Well Completed 6-18-62

Plugging Commenced 3-27-91

Plugging Completed 3-28-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Conoco, Inc.

ADDRESS 3817 N.W. Expressway, Oklahoma City, Ok 73112

PHONE#(405) 948-3100 OPERATORS LICENSE NO. 5916

Character of Well Inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-9-91 (date)

by David Williams (District 4) (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing Formation Lansing K.C. Depth to Top 3587' Bottom 3784' T.D. 3840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Saltwater	3520	3790'	8 5/8"	198'	<u>04-12-91</u> <u>APR 12 1991</u>
				5 1/2"	3839	

CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
See reverse side

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address N. Hwy. 281, P. O. Box 628 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Conoco, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Sonya C. Baker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sonya C. Baker

(Address) 3817 N.W. Expressway  
Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 10 day of April, 1991

Candy M. Oriscoll  
Notary Public

My Commission Expires: 7/22/92

Plugging Detail:

RU wireline & RIH w/ perf. gun shot 2 holes @ the top of Annhydrite 2130'. Shot 2 holes @ base of Dakota 1325'. POOH & RD wireline. RU Allies Cementers & tied onto 5 1/2" csg. Pumped 350 sx 65/35 Poz w/10% gel. Hooked up to surface pipe & pumped 100 sx 65/35 poz. TOC down 5 1/2" @ 280. Dumped 1.6 yds common cement down 5 1/2" to top. Cut and capped csg 5' below ground level. Cleaned & abandoned location. (KCC Rep,- Carl Goodrow.).

