

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

RECEIVED

AUG 31 2005

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: W.D. SHORT

Address: P.O. Box 729 OXFORD, KS. 67119

Phone: (620) 455-3576 Operator License #: 6679

Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8-25-04 (Date)

by: DAVID WILLIAMS (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 3143 Bottom: 3175 T.D. 3186

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-035-21,164-00-00

Lease Name: Anglemyer

Well Number: 1

Spot Location (QQQQ): C - SW - SE - NE

2310 Feet from ☒ North / ☒ South Section Line 8em

990 Feet from ☒ East / ☐ West Section Line 9-2-05

Sec. 28 Twp. 33 S. R. 5 ☒ East ☐ West

County: Cowley

Date Well Completed: 4-3-77

Plugging Commenced: 5-26-05

Plugging Completed: 6-23-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Mississippi</u>	<u>Oil</u>	<u>3143</u>	<u>3175</u>	<u>8 5/8"</u>	<u>203'</u>	<u>0</u>
				<u>4 1/2"</u>	<u>3229'</u>	<u>1645'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded back to 3100', Dumped 4sx cement on top of sand, shot 4 1/2" off
@ 1645' & Pulled Pipe, Pumped cement from 260' to surface (100sx)

Name of Plugging Contractor: B.P.C. Well Plugging License #: 32475

Address: P.O. Box 282 Burden, KS. 67019

Name of Party Responsible for Plugging Fees: W.D. SHORT

State of KANSAS County, Sumner, ss.

William D. Short, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 6 OXFORD, KS. 67119

SUBSCRIBED and SWORN TO before me this 21st day of August, 20 05

Notary Public

My Commission Expires: 3-30-09



B.P.C. WELL PLUGGING

P.O. BOX 282
BURDEN, KS 67019

RECEIVED
AUG 31 2005
KCC WICHITA

JAMES R. BRADEN
HOME # 620-438-2856 MOBILE # 620-222-1252

DATE	INVOICE #
7/28/2005	05/480

BILL TO
SHORT COMPANIES P.O. BOX 729 OXFORD,KS.67119

JOB LOCATION
ANGLEMAYER #1

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
5/26/2005		MOVED IN RIG. RIGGED UP TO PULL RODS, LAYED OUT IN SINGLES. RIGGED OVER TO PULL TUBING, LAYED OUT TUBING.	
5/27/2005		RIGGED UP TO PLUG BOTTOM. SANDED BACK TO 3100' DUMPED 4 SX. CEMENT ON TOP OF SAND WITH DUMP BAILER. DUG OUT CELLAR, SET JACKS UP. PULLED SLIPS, WORKED PIPE.	
5/31/2005		WORKED PIPE, SHOT OFF @ 1645'. LAYED OUT 41/2" PIPE. LOADED JACKS RIGGED DOWN.	
	RIG UP CHARGE		1,000.00T
	PIPE PULLING CHARGE	1645' OF 41/2" PIPE PILLED @ \$0.50 PER FT.	822.50T
	SHOOTING CHARGE	1 SHOT @ \$275.00 PER SHOT	275.00T
	RIG TIME	6 HRS. @ \$105.00 PER HR.	630.00T

Thank you for your business.		SUBTOTAL	\$2,727.50
		SALES TAX (5.3%)	\$144.56
		BALANCE DUE	\$2,872.06

B.P.C. WELL PLUGGING

P.O. BOX 282
BURDEN, KS 67019

RECEIVED
AUG 31 2005
KCC WICHITA

JAMES R. BRADEN
HOME # 620-438-2856 MOBILE # 620-222-1252

DATE	INVOICE #
7/28/2005	05/486

BILL TO
SHORT COMPANIES P.O. BOX 729 OXFORD,KS.67119

JOB LOCATION
ANGLEMAYER #1

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
6/23/2005		MOVED IN ON LOCATION. LOADED 40 BBL. FRESH WATER, RIGGED UP TO PUMP CEMENT. RUN 1" DOWN INSIDE 85/8" SURFACE PIPE TO 260'. PUMPED 100 SX. CEMENT, FILLED TO THE SURFACE. PULLED OUT 1", TOPPED OFF HOLE WITH CEMENT. WASHED UP, RIGGED DOWN.	
	CEMENT	100 SACKS- 4% GEL @ \$7.00 PER SACK	700.00T
	PUMP CHARGE	3 HRS @ \$75.00 PER HR.	225.00T
	BULK TANK	\$100.00 PER JOB	100.00T
	WATER TRUCK	3 HRS. @ \$50.00 PER HR.	150.00T

Thank you for your business.	SUBTOTAL	\$1,175.00
	SALES TAX (5.3%)	\$62.28
	BALANCE DUE	\$1,237.28