

RECEIVED

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

AUG 31 2005

Form CP-4  
December 2003

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

WELL PLUGGING RECORD KCC WICHITA

Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

K.A.R. 82-3-117

Lease Operator: W. D. SHORT

Address: P.O. BOX 729 OXFORD, KS. 67119

Phone: (620) 455-3576 Operator License #: 6679

Type of Well: OIL Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8-25-04 (Date)

by: DAVID WILLIAM (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 3112 Bottom: 3134 T.D. 3199  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API Number: 15-035-22035-00-00

Lease Name: Anglemyer

Well Number: 2

Spot Location (QQQQ): C - NE - SW - NE KCC BEM  
1650 3686 Feet from  North /  South Section Line 9.2.05

1650 1719 Feet from  East /  West Section Line GPS  
Sec. 28 Twp. 33 S. R. 5  East  West

County: Cowley

Date Well Completed: 10-21-78

Plugging Commenced: 6-1-05

Plugging Completed: 6-22-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	203	8 7/8"	203	0
		0	3199	4 1/2"	3199	1395'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

JANDED BACK TO 3060', DUMPED 4 SX CEMENT ON TOP OF SAND, SHOT OFF PIPE @ 1395', LAYED PIPE DOWN, PUMPED CEMENT FROM 250 TO SURFACE, 100 SX.

Name of Plugging Contractor: B.P.C. WELL PLUGGING License #: 32475

Address: P.O. BOX 282 BURDEN, KS. 67019

Name of Party Responsible for Plugging Fees: W. D. SHORT

State of KANSAS County, Sumner, ss.

WILLIAM D. SHORT, JR. (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) William D. Short, Jr.

(Address) P.O. BOX 6 OXFORD, KS. 67119

**DENESE A. WILSON**  
Notary Public - State of Kansas  
My Appt. Expires 3-30-09

SUBSCRIBED and SWORN TO before me this 29th day of August, 2005  
Denesa A. Wilson My Commission Expires: 3-30-09  
Notary Public

# B.P.C. WELL PLUGGING

P.O. BOX 282  
BURDEN, KS 67019

RECEIVED  
AUG 31 2005  
KCC WICHITA

<b>JAMES R. BRADEN</b>
HOME # 620-438-2856 MOBILE # 620-222-1252

<b>DATE</b>	<b>INVOICE #</b>
7/28/2005	05/481

<b>BILL TO</b>
SHORT COMPANIES P.O. BOX 729 OXFORD, KS. 67119

<b>JOB LOCATION</b>
ANGLEMAYER #2

<b>TERMS 30 DAYS</b>
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
6/1/2005		MOVED IN RIG. RIGGED UP TO PULL RODS, LAYED OUT IN SINGLES. RIGGED OVER TO PULL TUBING, LAYED OUT TUBING.	
6/2/2005		RIGGED UP TO PLUG BOTTOM. SANDED BACK TO 3060' DUMPED 4 SX. CEMENT ON TOP OF SAND WITH DUMP BAILER. DUG OUT CELLAR, SET JACKS UP. PULLED SLIPS, WORKED PIPE.	
6/3/2005		WORKED PIPE, SHOT OFF @ 1395'. LAYED OUT 4 1/2" PIPE. LOADED JACKS RIGGED DOWN.	
	RIG UP CHARGE		1,000.00T
	PIPE PULLING CHARGE	1395' OF 4 1/2" PIPE FILLED @ \$0.50 PER FT.	697.50T
	SHOOTING CHARGE	1 SHOT @ \$275.00 PER SHOT	275.00T
	RIG TIME	6 HRS. @ \$105.00 PER HR.	630.00T

<b>Thank you for your business.</b>	<b>SUBTOTAL</b>	\$2,602.50
	<b>SALES TAX (5.3%)</b>	\$137.93
	<b>BALANCE DUE</b>	<b>\$2,740.43</b>

# B.P.C. WELL PLUGGING

P.O. BOX 282  
BURDEN, KS 67019

RECEIVED  
AUG 31 2005  
KCC WICHITA

JAMES R. BRADEN
HOME # 620-438-2856 MOBILE # 620-222-1252

DATE	INVOICE #
7/28/2005	05/485

BILL TO
SHORT COMPANIES P.O. BOX 729 OXFORD,KS.67119

JOB LOCATION
ANGLEMAYER #2

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
6/22/2005		MOVED IN ON LOCATION. LOADED 40 BBL. FRESH WATER, RIGGED UP TO PUMP CEMENT. RUN 1" DOWN INSIDE 85/8" SURFACE PIPE TO 260'. PUMPED 100 SX. CEMENT, FILLED TO THE SURFACE. PULLED OUT 1", TOPPED OFF HOLE WITH CEMENT. WASHED UP, RIGGED DOWN.	
	CEMENT	100 SACKS- 4% GEL @ \$7.00 PER SACK	700.00T
	PUMP CHARGE	3 HRS @ \$75.00 PER HR.	225.00T
	BULK TANK	\$100.00 PER JOB	100.00T
	WATER TRUCK	3 HRS. @ \$50.00 PER HR.	150.00T

Thank you for your business.	<b>SUBTOTAL</b>	\$1,175.00
	<b>SALES TAX (5.3%)</b>	\$62.28
	<b>BALANCE DUE</b>	<b>\$1,237.28</b>