

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: BP AMERICA PRODUCTION COMPANY

Address: P.O. BOX 3092, Rm 3.315, HOUSTON, TX

Phone: Operator License # 5952

Type of Well: Gas Docket # (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: (KCC District Agent's)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number 15- 093-00076-00-00

Lease Name URIE

Well Number #1

Spot Location (QQQQ) NW NW NW SE

2490 Feet from North / South Line of Section

2490 Feet from East / West Line of Section

Sec. 8 Twp. 23S S. R. 35W East West

County: KEARNY

Date Well Completed: 10-11-52

Plugging Commenced: 07-19-05

Plugging Completed: 07-19-05

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out). Includes entries for SURFACE CASING and PRODUCTION CASING.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

7/19/05 - SET CIBP @ 2500'. DMP 4 SX OF CMT ON TOP OF PLUG. RAN CBL. NO CMT AT 1000'. PERF SOZ HOLES AT 950'. PMP INTO HOLES AT 3 BEM @ 500# WITH NO BLOW ON THE 10-3/4" X 7" ANNULUS. MIX & PMP 170 SX OF CMT TO FILL CSG FROM 0' TO 950'. PRS CSG TO 200#. MIX & PMP 60 SX DWN 10-3/4 X 7" ANNUL TO FILL ANNUL FROM 0'-270'. PRESSURE ANNUL TO 100#. CUT OFF & CAP CSG 5' BELOW GROUND LEVEL. RESTORE LOC. WITNESSED BY KCC REP., KEN JEHLIK.

Name of Plugging Contractor: HALLIBURTON SERVICES License # 5287

Address

Name of Party Responsible for Plugging Fees: BP AMERICA PRODUCTION COMPANY

State of TEXAS County, HARRIS, ss.

DEANN SMYERS (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Deann Smyers

(Address) P.O. BOX 3092, RM 3.201, HOUSTON, TX 77253-3092

SUBSCRIBED and SWORN TO before me this 25TH day of AUGUST, 20 05



ANN THOMPSON NOTARY PUBLIC, STATE OF TEXAS MY COMMISSION EXPIRES APR. 30, 2008

Ann Thompson Notary Public

My Commission Expires: 4-30-2008

Mail to: KCC, Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED SEP - 1 2005 KCC WICHITA

Bm