

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: W.D. SHORT
Address: P.O. Box 729 OXFORD, KS. 67119
Phone: (620) 455-3576 Operator License #: 6679
Type of Well: WATER Supply Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6-16-05 (Date)
by: DAVID WILLIAMS (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-035-19198-00-00
Lease Name: RAHN UNIT #1
Well Number: 8 NE NW
Spot Location (QQQQ): NE NW SE NE
1757 ⁴³⁷¹ Feet from North / South Section Line KCC
180 ³³⁵⁵ Feet from East / West Section Line 3EMV
Sec. 5 Twp. 34 S. R. 6 East West 9-1-05
County: Cowley GPS
Date Well Completed: 4-29-53
Plugging Commenced: 7-11-05
Plugging Completed: 7-28-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Water Sand</u>	<u>WATER</u>	<u>1113</u>	<u>1408</u>	<u>13"</u>	<u>200</u>	<u>0</u>
				<u>8 5/8"</u>	<u>1539</u>	<u>367</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand back to 1060' w/ sand, Dumped 10sx cement on top of sand, Shot off 8 5/8" and pulled pipe, Pumped cement from 350' to surface (195 sx)

Name of Plugging Contractor: B.P.C. Well Plugging License #: 32475
Address: P.O. Box 282 Burden, Ks. 67019

Name of Party Responsible for Plugging Fees: W.D. SHORT
State of KANSAS County, Sumner, ss.

William D. Short, Jr.
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 6 OXFORD Ks. 67119

RECEIVED
SEP - 1 2005
KCC WICHITA

DENESE A. WILSON Notary Public - State of Kansas
My Appt. Expires 3-30-09
SUBSCRIBED and SWORN TO before me this 20th day of August, 2005
[Signature] Notary Public My Commission Expires: 3-30-09

B.P.C. WELL PLUGGING

P.O. BOX 282
BURDEN, KS 67019

JAMES R. BRADEN
HOME # 620-438-2856 MOBILE # 620-222-1252

DATE	INVOICE #
8/2/2005	05/490

BILL TO
SHORT COMPANIES
P.O. BOX 729
OXFORD,KS.67119

JOB LOCATION
COX #8

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
7/11/2005		MOVED IN ON LOCATION, RIGGED UP TO PLUG BOTTOM. HAD TROUBLE GETTING BAILER TO BOTTOM. STARTED SAND IN, BRIDGE OFF @ 450'. TRIED TO KNOCK OUT WITH BAILER. NO LUCK.	
7/13/2005		RIGGED UP TO RUN TUBING. RUN IN TO TOP OF BRIDGE. CIRCULATED DOWN. WASHED ON HOLE. RUN TUBING ON TO BOTTOM. WASH OUT HEAVY MUD & SAND, CLEAN HOLE.	
7/14/2005		LAYED OUT TUBING. SANDED BACK BOTTOM TO 1060'. DUMPED 10 SX. OF CEMENT ON TOP OF SANDED WITH DUMP BAILER. SET JACKS, WORKED PIPE. SHOT @ 367' PIPE WOULDN'T COME. SHOT @ 337' PIPE WOULDN'T COME.	
7/15/2005		RESHOT 367' WOULDN'T MOVE. SHOT AGAIN 367' PIPE WOULDN'T COME. SHOT 337' PIPE WOULDN'T PULL. SHOT @ 307' PIPE MOVED REAL TIGHT.	
7/21/2005		BLEW SEAL OUT OF PUMP. SHUT DOWN. MOVING PIPE, PIPE WOULDN'T BREAK LOOSE. CUT OFF WITH TORCH. LAYED OUT 85/8" PIPE. COME OUT WITH 367'. LOADED UP JACKS, RIGGED DOWN.	
	RIG UP CHARGE		1,000.00T
	PIPE PULLING CHARGE	1000' MINIMUM @ \$0.50 PER FT.	500.00T
	SHOOTING CHARGE	6 SHOT @ \$275.00 PER SHOT	1,650.00T
	RIG TIME	5 HRS. @ \$105.00 PER HR.	525.00T

RECEIVED
SEP - 1 2005
KCC WICHITA

Thank you for your business.	SUBTOTAL
	SALES TAX (5.3%)
	BALANCE DUE

B.P.C. WELL PLUGGING

P.O. BOX 282
BURDEN, KS 67019

JAMES R. BRADEN
HOME # 620-438-2856 MOBILE # 620-222-1252

DATE	INVOICE #
8/2/2005	05/490

BILL TO
SHORT COMPANIES P.O. BOX 729 OXFORD,KS.67119

JOB LOCATION
COX #8

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
	WELDER	2 HR. @ \$50.00 PER HR.	100.00T

RECEIVED
SEP - 1 2005
KCC WICHITA

Thank you for your business.

SUBTOTAL	\$3,775.00
SALES TAX (5.3%)	\$200.08
BALANCE DUE	\$3,975.08

B.P.C. WELL PLUGGING

P.O. BOX 282
BURDEN, KS 67019

JAMES R. BRADEN
HOME # 620-438-2856 MOBILE # 620-222-1252

DATE	INVOICE #
8/2/2005	05/493

BILL TO
SHORT COMPANIES P.O. BOX 729 OXFORD,KS.67119

JOB LOCATION
COX # 8

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
7/26/2005		MOVED IN ON LOCATION. LOADED 40 BBL. FRESH WATER. RIGGED UP TO PUMP CEMENT. RUN 1" DOWN INSIDE 13" SURFACE PIPE TO 350'. PUMP 145 SX CEMENT OUT OF WATER NOT ENOUGH CEMENT LEFT.	
7/28/2005		LOADED 40 BBL. FRESH WATER. RUN 1" IN HOLE FOUND CEMENT 90' DOWN PUMPED 50 SX. CEMENT FILLED TO THE SURFACE. PULLED OUT 1" TOPPED OFF WITH CEMENT. WASHED UP RIGGED DOWN.	
	CEMENT	195 SACKS- 4% GEL @ \$7.00 PER SACK	1,365.00T
	PUMP CHARGE	4 HRS @ \$75.00 PER HR.	300.00T
	BULK TANK	\$100.00 PER JOB	100.00T
	WATER TRUCK	5 HRS. @ \$50.00 PER HR.	250.00T

RECEIVED
SEP - 1 2005
KCC WICHITA

Thank you for your business.	SUBTOTAL	\$2,015.00
	SALES TAX (5.3%)	\$106.80
	BALANCE DUE	\$2,121.80