

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED

SEP 02 2005

KCC WICHITA

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: B.L.G. Company  
Address: P.O. Box 214  
Phone: (785) 483-2276 Operator License #: 5358  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: August 22, 2005 (Date)  
by: Virgil Clothier (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 2597' Bottom: 3293' T.D. 3313'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-053-20775-00-00  
Lease Name: Stoltenberg  
Well Number: #9  
Spot Location (QQQQ): NW SE  
-N1/2- S1/2- SE 9-7-05  
RBOMS  
CP2/3  
990' Feet from  North /  South Section Line  
1320' Feet from  East /  West Section Line  
Sec. 33 Twp. 16 S. R. 10  East  West  
County: Ellsworth  
Date Well Completed: 7/21/1982  
Plugging Commenced: 8/23/05  
Plugging Completed: 8/29/05

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	409.58'	8-5/8"	409.58'	0'
	Production	0'	3282'	5-1/2"	3282'	1192.38'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Put sand down casing - ran bailer. Mixed up 5 sx cement. Plugged back to 3230'. Moved jacks over casing. Pulled slips out of casing head. Worked casing. Showing of 1200' of casing. Rigged up knife to cut casing. Ran knife in 5-1/2" casing to 1500'. Made cut in collar. Worked casing-no change. Trip back in hole with knife to 1200'. Cust casing collar-came loose. Pulled 5 joints of casing. Rigged up Copeland. Spot 35 sx cement. Pulled up to 1000'-spot 35 sx cement; pulled up to 460'-130 sx cement. Pulled rest of casing-tallied. Recovered 1192.38' of casing. R.D.M.O.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901  
Address: P.O. Box 231, Claflin, Kansas 67525  
Name of Party Responsible for Plugging Fees: B.L.G. Company  
State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

  
KAREN J. MITCHELL  
Notary Public - State of Kansas  
My Appt. Expires 4/13/06

Signature: Edward S. Nemnich  
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 1st day of September, 20 05  
Karen J. Mitchell My Commission Expires: 4/13/06  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Bu*