

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market - Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-067-20635-0000

LEASE NAME MATZEN

WELL NUMBER 3-28

2100' FSL Ft. from S Section Line

1280' FWL Ft. from E Section Line

SEC. 28 TWP. 30S RGE. 38W (E) or (W)

COUNTY GRANT

Date Well Completed 03/12/87

Plugging Commenced 8/26/05

Plugging Completed 8/29/05

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (972) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/20/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 3177' KB Bottom 2853' T.D. 2960'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2424'	2738'	8 5/8"	657'	0
				5 1/2"	2946'	885'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

8/26&29/05 Witnessed by J Holland, KCC. Set CIBP @2375' KB, spot 20' cmt. Revise PBDT @2355'. NU cmtr to 5 1/2" csq, load hole w/16 bbl mud to 1700' & 20 sx cmt plug frm 1700'-1540'. Cut csq at 885'. Circ w/ 20 bbl mud. Pmp 50 sx cmt plug 675'-525' & displ w/12 bbl mud. Load hole w/4 bbl mud to 40' & 10 sx cmt 40'-0'. Cut 8 5/8" surf csq 3' bgl, weld on trash cover-ID plate.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



SWORN TO before me this 31st day of August, 20 05

My Commission Expires: 4/2/09

Deborah Pollock  
Notary Public

USE ONLY ONE SIDE OF EACH FORM

RECEIVED  
SEP 02 2005  
KCC WICHITA

Form CP-4  
Revised 05-88

*Bm*