

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED  
SEP 02 2005  
KCC WICHITA  
Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: PETROSANTANDER (USA) INC  
Address: 6363 Woodway #350, Houston, Texas 77057  
Phone: (713) 784-8700 Operator License #: 32198  
Type of Well: D&A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 07-24-05 (Date)  
by: Ken Jehlick (witnessed by R. Lacey) (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-119-21158-00-00  
Lease Name: STEVENS (MORROW) UNIT  
Well Number: SMU 3605B  
Spot Location (QQQQ): \_\_\_\_\_ - SW - SW - SW  
2600 Feet from  North /  South Section Line  
150 Feet from  East /  West Section Line  
Sec. 36 Twp. 32 S. R. 30  East  West  
County: MEADE  
Date Well Completed: 07-24-05  
Plugging Commenced: 07-24-05  
Plugging Completed: 07-24-05

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	1540	8 5/8"	1540'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 1450' w/50 sks  
2nd Plug @ 500' w/40 sks  
3rd Plug @ 40' w/10 sks  
Rat Hole w/15sks Mouse hole w/10 sks Total 125sks 60/40 Poz w/4% gel

Name of Plugging Contractor: Allyed Cementing Co. Cheyenne Drilling License #: NA 33375  
Address: PO Box 31, Russell, Kansas 67665  
Name of Party Responsible for Plugging Fees: Petrosantander  
State of Texas County, Harris, ss.  
Thomas W Nelson

KCC  
BEAM  
9-7-05  
RBDms  
Per CMT  
Ticket  
CP 213



\_\_\_\_\_  
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct to the best of my knowledge and belief, so help me God.  
(Signature) Tom Nelson  
(Address) 6363 Woodway #350, Houston, Texas 770057

SUBSCRIBED and SWORN TO before me this 31<sup>st</sup> day of AUGUST, 2005  
Alan Edwards My Commission Expires: Sept 19 / 2007  
Notary Public

Bur

# ALLIED CEMENTING CO., INC.

16212

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
M.L.

DATE <u>7-24-05</u>	SEC. <u>31e</u>	TWP. <u>32s</u>	RANGE <u>30W</u>	CALLED OUT <u>1:30 pm</u>	ON LOCATION <u>4:00 pm</u>	JOB START <u>5:15 pm</u>	JOB FINISH <u>7:45 pm</u>
LEASE <u>Smg</u>		WELL # <u>3605b</u>	LOCATION <u>Plains</u>	<u>3south - 2east</u>		COUNTY <u>Maize</u>	STATE <u>KS</u>
OLD OR NEW (Circle one)							

CONTRACTOR Cheyenne #1

TYPE OF JOB Rotary Plug

HOLE SIZE 7 7/8" T.D. 1450'

CASING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE 4 1/2" DEPTH 1450'

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 200 MINIMUM 50

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT Mud / H<sub>2</sub>O

EQUIPMENT \_\_\_\_\_

PUMP TRUCK # 352 CEMENTER Mike Rucker

BULK TRUCK # 389 HELPER Tracy Cushmanburg

BULK TRUCK # \_\_\_\_\_ DRIVER Steve O

BULK TRUCK # \_\_\_\_\_ DRIVER \_\_\_\_\_

OWNER Petrosantander USA

CEMENT AMOUNT ORDERED 125x 60:40:10

COMMON	<u>75 A</u>	@	<u>8.70</u>	<u>652.50</u>
POZMIX	<u>50</u>	@	<u>4.70</u>	<u>235.00</u>
GEL	<u>7</u>	@	<u>14.00</u>	<u>98.00</u>
CHLORIDE		@		
ASC		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>132</u>	@	<u>1.60</u>	<u>211.20</u>
MILEAGE	<u>35 X 132 X .06</u>	@		<u>277.20</u>
TOTAL				<u>1473.90</u>

RECEIVED  
SEP 02 2005  
KCC WICHITA

### REMARKS:

1<sup>st</sup> Plug 1450' 5:15 pm load hole. Pump fresh ahead mix 50x 60:40:10 @ 13.8 weight. Displace with mud.

2<sup>nd</sup> Plug: 500' 6:00 pm load hole. Pump fresh ahead mix 40x 60:40:10 @ 13.8 weight. Displace with fresh

3<sup>rd</sup> Plug: 40' 7:15 pm load hole mix 10x 60:40:10 Displace with fresh 7:45 pm. Mix 15x 60:40:10 @ 13.8 Rathole. Mix 10x 60:40:10 @ 13.8 mouse hole.

### SERVICE

DEPTH OF JOB	<u>1450'</u>			
PUMP TRUCK CHARGE				<u>665.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>35</u>	@	<u>5.00</u>	<u>175.00</u>
		@		
		@		
		@		

CHARGE TO: Petrosantander USA

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL 840.00

### PLUG & FLOAT EQUIPMENT

MANIFOLD		@		
		@		
		@		
		@		
		@		

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

TAX				
TOTAL CHARGE				<del>1473.90</del>
DISCOUNT				<del>633.90</del> IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME Mike Colaneri

Thank you!

# ALLIED CEMENTING CO., INC.

22138

Federal Tax I.D.# ~~48-111862~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>7-17-05</u>	SEC <u>36</u>	TWP. <u>32S</u>	RANGE <u>30W</u>	CALLED OUT	ON LOCATION <u>12:30PM</u>	JOB START <u>3:10PM</u>	JOB FINISH <u>4:10PM</u>
STEVEN MORROW LEASE <u>Unit</u>	WELL# <u>3605 B</u>	LOCATION <u>Plains 3S 26 1/2 N E1S</u>			COUNTY <u>Meade</u>	STATE <u>KS</u>	
OLD OR <u>(NEW)</u> (Circle one)							

CONTRACTOR Cheyenne Drlg Rig 1  
 TYPE OF JOB Surface  
 HOLE SIZE 12 1/8 T.D. 1540'  
 CASING SIZE 8 7/8 DEPTH 1539'  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 800# MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT 44.82'  
 CEMENT LEFT IN CSG. 44.82'  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT 95 1/4 Bbls

OWNER S 9 ml  
 CEMENT  
 AMOUNT ORDERED 150 SKS COM 3 2nd CC  
600 SKS Lite 3rd CC 1/4" Flo Seal

COMMON	<u>150 SKS</u>	@	<u>8.70</u>	<u>1305.00</u>
POZMIX		@		
GEL		@		
CHLORIDE	<u>25 SKS</u>	@	<u>38.00</u>	<u>950.00</u>
ASC		@		
	<u>Liteweight 600SKS</u>	@	<u>8.15</u>	<u>4890.00</u>

	<u>Flo Seal 150 #</u>	@	<u>1.70</u>	<u>255.00</u>
--	-----------------------	---	-------------	---------------

RECEIVED \_\_\_\_\_ @ \_\_\_\_\_

SEP 02 2005 \_\_\_\_\_ @ \_\_\_\_\_

KCC WICHITA \_\_\_\_\_ @ \_\_\_\_\_

HANDLING	<u>775 SKS</u>	@	<u>1.60</u>	<u>1240.00</u>
MILEAGE	<u>6 # / SK / mile</u>			<u>1627.50</u>

TOTAL 10267.50

EQUIPMENT  
 PUMP TRUCK CEMENTER Dean  
 # 373-281 HELPER Andrew  
 BULK TRUCK  
 # 353 DRIVER Steve  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

Cemented 8 7/8 w/ 600SKS Lite  
3rd CC 1/4" Flo Seal + 150SKS com  
3rd CC Release Plug + Drop w/ 95 1/4 Bbls  
Cement did circulate & articulate  
25 Bbls cement to bit  
Plug landed 800#  
Plug held.  
Thank you

SERVICE

DEPTH OF JOB	<u>1539'</u>		
PUMP TRUCK CHARGE			<u>1320.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>35 miles</u>	@	<u>5.00</u> <u>175.00</u>
MANIFOLD		@	
		@	

TOTAL 1495.00

CHARGE TO: Petro Santander (USA) Inc

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

<u>Guide shoe</u>			<u>235.00</u>
<u>API Insert</u>	@		<u>325.00</u>
<u>3 - Centralizers</u>	@	<u>55.00</u>	<u>165.00</u>
<u>1 - Basket</u>	@		<u>180.00</u>
<u>8 7/8 Rubber Plug</u>	@		<u>100.00</u>
	@		

TOTAL 1005.00

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

PRINTED NAME \_\_\_\_\_

*PetroSantander (USA) Inc.*

RECEIVED  
SEP 02 2005  
KCC WICHITA

August 31<sup>st</sup>, 2005

Kansas Corporation Commission  
Conservation Division  
Wichita State Office Building  
130 S. Market, Room 2078  
Wichita, KS 67202-3802

Attn:- Barbara Montgomery

Re: **Request for Information**  
Well Plugging Record Form CP-4 for:SMU 3605B  
Sec 7-T23S-R30W, Finney County, Kansas

Dear Barbara:

This is to fulfill your request that all of the information that PetroSantander (USA) Inc. has provided on the old CP-4 form be re-submitted on the new Form. As discussed with you on the phone all our information is correct apart from the District Office witness. I have enclosed the cement tickets for the plugging as supplied by Allied Cement Co. in order that you may verify the information provided to your office.

Should you have any questions, please feel free to contact the undersigned at (713) 784-8700.

Very truly yours,  
PetroSantander (USA) Inc.



Alan Edwards  
Operations Assistant

*PetroSantander (USA) Inc.*