

15-193-20042-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company has this
date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Murfin Drlg. Co., Patrick Petroleum & Carnahan,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Goetsch Well No. 1

Location: App:-CSE-SW Sec. 35 Twp. 6 Rge. (E)(W) 36

County: Thomas Total Depth 3045' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

293'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1700'.

Circulate hole with heavy mud. Pull DP to 1925' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

R. L. Nichols

Conservation Division Agent