



15-193-20036-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 5 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
4-571

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Oller of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: McCormick Theological Seminary Well No. 1

Location: CNW-NW Sec. 35 Twp. 6 Rge. (E)(W) 36

County: Thomas Total Depth 4200' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Oller was instructed to plug the well as follows:

303'--8 5/8" Surface casing, cement circulated with 250 Sx.

Circulate hole with heavy mud. Pull DP to 1250' and displace 100 Sx.

cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Deibel  
Conservation Division Agent