



15-193-20022-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 19 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
9-19-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Inc., has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Graves Drilling Company, Inc.

Complete Address: 505 Union Center Building, Wichita, Kansas.

Lease Name: Roulier Well No. 1

Location: 300' N. of CSE-NE Sec. 35 Twp. 6 Rge. (E)(W) 36

County: Thomas Total Depth 4932' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

320'--8 5/8" Surface casing, cement circulated with 300 Sx.  
Top of Dakota section @ 1700'.

Circulate hole with heavy mud. Pull DP to 1900' and displace 100 Sx.  
cement thru DP. Pull DP to 330' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent