



13-181-05041-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1971
CONSERVATION DIVISION
Wichita, Kansas

2-16-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. W. A. Mills of Phillips Petroleum Company has this date requested permission to plug the following described well:

Mr. Mills guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name: Llanos Well No. 3

Location: /CNE-NW Sec. 10 Twp. 6 Rge. (E)(W) 37

County: Sherman Total Depth 4950' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Mills was instructed to plug the well as follows:

360'--9 5/8" Surface casing, cement circulated. (8 3/4" Hole).

4844'--7" Oil Production casing cemented on bottom with 230 Sx. Well Plugged back to 4657'. Perforations from 4436' to 4652'.

Run 2" tubing to bottom and displace 70 Sx. cement thru tubing. Pull 7" casing and squeeze well with 5 sacks hulls, 70 sacks gel and 200 Sx. cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent