

State of Kansas



15-181-05039-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1968
CONSERVATION DIVISION
Wichita, Kansas

8-27-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cleo Long of Phillips Petroleum Company has this date requested permission to plug the following described well:

Mr. Long guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name: Llanos Well No. 1

Location: W/2-NW-NE Sec. 10 Twp. 6 Rge. (E)(W) 37

County: Sherman Total Depth 4960 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Long was instructed to plug the well as follows:

370'--8 5/8" Surface pipe, cement circulated.
5000'--4 1/2" Drill pipe set for production string cemented on bottom with
160 Sx. Stage collar set @ 2791' cement circulated to surface with 350 Sx.
Top perforations from 4804 to 4812'.

Sand well back to 4750' and set 2 Sx. cement with dump bailer. Push plug
to 1650', sand back to 1625' and set 2 Sx. cement with dump bailer. let
plugs set overnight and fill to surface with 6 yards Redi-Mix cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent