

State of Kansas



15-181-05053-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1967

2-20-67

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Mike Wasinger of Knights Casing Pulling Co. has this

date requested permission to plug the following described well:
Phillips Petr. Co.

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: P.O. Box #287, Great Bend, Kansas.

Lease Name: Hartley Well No. A-4

Location: CNW-SE Sec. 3 Twp. 6 Rge. (E)(W) 37

County Sherman Total Depth 4996 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

378'-- 9 5/8" Surface pipe, cement circulated.
4861'--7 " OD Production casing cemented. Temperature Survey
shows top of cement @ 3090'. Well plugged back to 4796'. Top
perforations from 4778' to 4784'.

Sand well back to 4760' and set 5 Sx. cement with dump bailer.
Pull 7" casing, set rock bridge @ 400' and dump 3 yards Redi-
Mix cement. Fill hole with mud to 50' and 1 yard Redi-Mix to
bottom of cellar.

Very truly yours,

K. L. Nichols
Conservation Division Agent