



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 26 1963
 2-26-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co has this

date requested permission to plug the following described well:
Phillips Petroleum Co

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Co

Complete Address: Box #779, Great Bend, Kansas

Lease Name: Hartley Well No. A-3

Location: SE-SE Sec. 3 Twp. 6 Rge. (E) (W) 37

County Sherman Total Depth 4972 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

363' 9 5/8" Surface, cement circulated, 7" to 4970', plugged
back to 4516', Perforations 4480' to 4486'. Sand well back
to 4465', set 4 Sx cement w/dump bailer. Pull casing to 600',
circulate heavy gel mud and displace 25 Sx cement thru 7",
Pull 7" to 360' and displace 25 Sx cement thru 7", Pull casing
set bridge @ ~~xx~~ 35' and 10 Sx cement to bottom of cellar.

Very truly yours,

W. L. Dechler
 Conservation Division Agent