

15-179-05163-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1975

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner PETROLEUM MANAGEMENT, INC.

Address 400 N. WOODLAWN, SUITE 201, WICHITA, KANSAS 67208

Lease (Farm Name) ADELL Well No. 202

(E/2 SW SE)

Well Location SE/4 Sec. 12; Twp. 6S Rge. (E) (W) 27

County Sheridan Total Depth 3790' Field Name ADELL

Oil Well Gas Well Input Well XX SWD Well Rotary D & A

Well Log filed with application as required attached

Date and hour plugging is desired to begin unknown

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Donald H. Keener Address 2305 Walnut, Hays, Ks. 67601

Plugging Contractor Petroleum Management, Inc. License No. 731

Address P. O. Box 1325, Great Bend, Kansas 67530

Invoice covering assessment for plugging this well should be sent to:

Name PETROLEUM MANAGEMENT, INC.

Address P. O. BOX 1325, GREAT BEND, KANSAS 67530

and payment will be guaranteed by applicant or acting agent.

Signed: 
Applicant or Acting Agent

Date: Jan. 23, 1975

IMPERIAL OIL & KANSAS, INC.
Well Completion Report

TRACT 2
Schoen Lease. Well No. 2
Loc. E/2 SW SE Sec. 12 Twp. 6S Rge. 27W
County Sheridan State Kansas
Pool Adell

Spud Date 9-16-57
Rotary Completed 9-27-57
Completion Date 10-8-57
Potential 247 BOPH-1W
Gravity 40
R. T. D. 3790

Surface casing set at (8 5/8) 219 with 175 sacks
Production casing set at (5 1/2) 3790 with 150 Sacks

Formation Tops: 2583 RB
Elevation:

Sample Electric Log

Anhydrite	2130 (+453)	2130 (+453)
Heebner	3535 (-952)	3539 (-956)
Toronto	3558 (-975)	3560 (-977)
Lansing	3572 (-989)	3578 (-995)

PRODUCING AND PROSPECTIVE PRODUCING ZONES

Formation	Depth	Feet	Remarks	Estimated Reserves
Lansing				
Top	3580-84	4	DST #3 3568-3600 L hr. Rec. 8' M BHP 0#	
35' Z	P. 3612-15	3	Open	
50' Z	P. 3622-26	6	Open	
90' Z	3650-54	4	DST #6 3634-56 2 hrs. Rec. 230' G 130' HOCM BHP 510#	
100' Z	P. 3664-68	4	Open	
140' Z	P. 3696-3702	2	Open	
180' Z	P. 3730-35	5	Open	
200' Z	P. 3753-56	6	Open	

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1975
CONSERVATION DIVISION
Wichita, Kansas

Completion Data: 9-29-57

Moved in; rigged up. Swabbed hole down. Logged well by Halliburton to TD of 3766. Perforated 200' zone with 9 Bullets + 12 Jets 3753-56. Show of oil natural. Treated with 250 gal. Jel-W. Highest pressure 250#. Input 1/2 bbl. per min. Pressure dropped to 0# in 1 min. Let. well set 3 hrs. Swabbed hole down.

Re30-57

8 hr. swab test 4 1/2 BOPH - NW. Perforated 180' zone with 15 Bullets + 16 Jets from 3730-35. Ran tubing with packer set at 3742. Treated 200' zone with 2500 gal. Jel-B. Highest pressure 850#. Pressure dropped to 350# in 5 min. Treated 180' zone with 1000 gal. J-type + 2500 gal. Jel-B. Highest pressure 550#. Pressure dropped to 250# in 3 min. All indications show well is not channeled between the 180' & 200' zones. Pulled tubing and removed packer.

10-1-57

Let well set 6 hrs. Swabbed hole down. 4 hr swab test 25 BOPH 700' off bottom - no wtr. Set Halliburton retrievable packer at 3714 between 140' & 180' zones. Perforated 140' zone from 3696-3702 with 15 Bullets + 20 Jets. 8 hr. swab test well making 19 BOPH 700' off packer.

10-2-57

Removed packer. 4 hr. swab test well still making 19 BOPH 700' off bottom. All indications show well channeled between 140' & 180' zone.

10-3-57

Ran retrievable packer back set at 3742 between 180' & 200' zone. Ran tubing with packer set at 3718 between 140' & 180' zone. Treated 180' zone with 1000 gal. J-type + 2000 gal. Jel-B using 1000 gal. Form Jel on 140' zone. Highest pressure on 140' zone 500#. treating 180' zone with 1000 gal J-type. Treated on vacuum. After Jel-B on formation started using pressure highest pressure 750#. Pressure dropped to 0# when pump stopped.

State of Kansas



15-179-05163-00-08

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

January 27, 1975

RENEWAL AUTHORITY
MaY 24, 1976 - cls

WELL PLUGGING AUTHORITY

Well No. 202
Lease Adell
Description E/2 SW SE 12-6-27W
County Sheridan
Total Depth 3790'
Plugging Contractor Petroleum Management, Inc.

Petroleum Management, Inc.
P. O. Box 1325
Great Bend, Kansas 67530

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P. O. Box 9, Rt. #1, Pálco, KS 67657
is hereby assigned to supervise the plugging of the above named well.