

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1976
09-13-1975
CONSERVATION DIVISION
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

15-179-05515-00-00

Lease Owner Continental Oil Company

Address 3535 NW 58th St., Oklahoma City, Okla. 73112

Lease (Farm Name) Adell Lansing KC Unit Well No. 208

Well Location Appt C NW NW SW
2250' FSL & 330' FWL Sec. 12 Twp. 6S Rge. (E) 27 (W)

County Sheridan Total Depth 3910' Field Name Adell

Oil Well Gas Well Input Well X SWD Well Rotary D & A

Well Log filed with application as required Yes

Date and hour plugging is desired to begin Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Mr. John Wright Address Plainville, Kansas

Plugging Contractor Unknown License No.

Address

Invoice covering assessment for plugging this well should be sent to:

Name Mr. H. S. Miles

Address P.O. Box 267, Great Bend, Kansas 67530

and payment will be guaranteed by applicant or acting agent.

Signed: *J. Cook*
Applicant or Acting Agent

Date: September 9, 1976

15-17-05615-00-00

CONTINENTAL OIL

PRODUCTION & MILLING DEPT.

NEW WELL COMPLETION AND/OR ABANDONMENT RECORD

A.F.E. NO. 5-61-7661

1 Dist. Plainville Field Adell Lease Adell Lansing-KC Unit Well No. 208 IWA
 2 Co. Sheridan State Kansas Contractor Barnett Drig. Co. T.D. 3910 P.D. 3868 ft.
 3 GL 2643 Elev. + GL 2643 ft. Depth Measured From HP 2652; Height of Measuring Point from GL 9 ft.
 4 Date: Spudded 5-21-62 Drilling Completed 5-22-62 Tested 6-5-62 Rig Released 5-30-62

CASING, LINER AND TUBING RECORD

5	SIZE O. D. IN.	WT. LB./FT.	THREADS NO. & TYPE	GRADE AND MAKE	NEW OR S. H.	E. L. L. W. SMLS.	DEPTH SET FT.	MEASUREMENTS INC. THREADS			TOP OF LINER	NO. OF JOINTS	HOLE SIZE
								QUANTITY SET	QUANTITY PULLED	QUANTITY LEFT IN HOLE			
6	8 5/8	24	8 RT	J-55	New	SMLS	196	186	None	186		6	12 1/4
7	5 1/2*	14	8 RT		New	E.W.	3906	3930	None	3930		123	7 7/8
8	2 3/8*	4.6	10 RT	J-55	New		3767	3778	None	3778		121	
9	*Limited Service Pipe												

CEMENTING RECORD

14	METHOD	MAKE AND TYPE CEMENT	SACKS USED	SQUEEZED AWAY	NO. OF BATCHES	FINAL PRESSURE	SLURRY WT. LB./GAL.	HOURS SET	DEPTH		REMARKS: TEMP. CALIPER, OTHER LOGS
									FROM	TO	
15	Pump	Common	200	-	1			24	196	0	Surface Pipe Prod. Casing
16	"	Pozmix	225*	-	1			48	3906		
17	*Plus 17% Salt and 225 lbs. Halad No. 9										

ACIDIZATION AND SHOT RECORD

19	DATE	PRODUCTION OR P. I.		HOW TEST MADE	GAL. ACID	SHOT QTS.	DEPTH		NAME OF ZONE	TYPE FORMATION	REMARKS
		BEFORE	AFTER				FROM	TO			
20	See Reverse Side										

SECTION PERFORATED

23	NAME OF PAY	DEPTH		SIZE OF HOLE	HOLES PER FOOT	DATE	SERVICE CO. OR TYPE SLOTS	REMARKS
		FROM	TO					
24	See Reverse Side							

No - PRODUCING EQUIPMENT

29 RODS: Number _____ Size _____ in., Number _____ Size _____ in., Total Singles _____ Length _____ ft.
 30 PUMP: Size _____ Plunger Diam. _____ Make _____ Type _____
 31 PUMPING UNIT: Make _____ Type _____ Stroke _____ in. @ _____ SPM; Beam Capacity _____ lb.
 32 Torque @ 20 SPM _____ in. lbs.; Gear Box _____ H.P., Prime Mover Make _____
 33 H.P. @ _____ RPM. Other Remarks _____
 34 GAS ANCHOR _____
 35 OTHER LIFT EQUIPMENT _____

36 _____
 37 PACKER: Set at 3767 ft. Make Baker Model - G Packer with Hold-down { ALSO SEE SKETCH }
 { ON REVERSE SIDE }

PRODUCING STRATA

38	NAME	TOP	BASE	POROSITY %	PERM. MD.	NET THICKNESS FT.	REMARKS: STATE CONTENTS OF ALL PRODUCING STRATA, O. G. & W. GIVING FLUID CONTACTS, D. S. T., ETC.

40
41
42
43 REMARKS: LOCATED: 2250' from the South and 330' from the West lines of Sec. 12,
T6S, R27W
 44
 45
 46 TD: 3910' PB: 3868'

47 Input Interval: Lansing-KC Perforations
 48
 49
 50
 51
 52
 53
 54
 55

56 Estimate Total Cost \$ 28,998 Conoco Interest 100% Operated by Continental Oil Company
 57 Potential _____ b/d/Mcf/d @ _____ #TP and #CP on _____ Hr. Test Meas. Est. Allowable _____ b/d
 58 Other Production or Well Test Results _____
 59

60 Signed [Signature] District Superintendent
 61 Signed C. R. WALLEN Division Superintendent
 62 Signed _____ Region Manager
 63 Signed _____ District Engineer
 64 Prepared by A. R. Colpitt - mc Date 10-22-62

DISTRIBUTED TO
 JPM Acct'g CES
 CRW District LEP
 RCB
 Others _____

15-179-05515-00-00

ACIDIZATION RECORD

Date	Production or P.I.		How Test Made	Gal. Acid	Depth		Name of Zone	Type Formation	Remarks
	Before	After			From	To			
6-3-62	-	2	GPM Vac	Pump	375	3847-48'	Lans-KC	Lime	5% Acid
6-4-62	-	3	GPM Vac	Pump	225	3651-52'	"	"	5% Acid
6-4-62	-	3½	GPM Vac	Pump	175	3651-52'	"	"	5% Acid

SECTION PERFORATED

Name of Pay	Depth		Holes Per Foot	Date	Service Company
	From	To			
Lansing-KC	3847-3848'		4	6-2-62	Lane-Wells
"	3651-3652'		4	6-4-62	" "
"	3682-3683'		4	6-4-62	" "
"	3692-3693'		4	6-4-62	" "
"	3807-3808'		4	6-4-62	" "
"	3826-3827'		4	6-4-62	" "

BRIEF ACCOUNT OF WORK DONE

Type: IWA. TD: 3910'. 5 1/2" Casing set at 3906' with 225 sacks of Pozmix, plus 17% salt and 225 lbs. Halad No. 9. SPD: 5-21-62, Drilling completed 5-29-62. Electric Log Tops: Heebner 3608', Toronto 3635', Lansing-KC 3650'. Perforated the Lansing-KC as follows: "A" 3651-52', "B" 3682-83', "D" 3692-93', "I" 3807-08', "J" 3826-27', "K" 3847-48'. Acidized with total of 775 gals. of 5% acid. Water injection rate tested satisfactory 6-5-62. RBE: 2652', RB/GL: 9'.



State of Kansas



15-179-05515-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

September 13, 1976

WELL PLUGGING AUTHORITY

Well No.	208
Lease	Adell Lensing KC Unit
Description	App./C NW NW SW Sec. 12-6-27W
County	Sheridan
Total Depth	3910
Plugging Contractor	Unknown


Continental Oil Company
3535 NW 58th Street
Oklahoma City, Oklahoma 73112

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above
named well.