

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-163-00216-00-00

WELL PLUGGING APPLICATION FORM

Lease Owner Cyrus N. Peterson Address Luray, Kansas
(Applicant)

Lease (Farm Name) D. N. Hardman Well No. 1

Well Location NW NE NE Sec. 34 Twp. 7 Rge. (E) or (W) 16

County Rooks Field Name (if any) _____

Was well log filed with application? yes. If not, explain: _____

Date and hour plugging is desired to begin _____

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired. (Use an additional sheet if necessary) _____

Name of the person on the lease in charge of well for owner _____

O. G. Stearns Address Russell, Kansas

Name of Plugging Contractor Stearns Petroleum, Inc.,

Address Russell, Kansas

Invoice covering assessment for plugging this well should be sent to:

Stearns Petroleum, Inc., Address Russell, Kansas

and payment will be guaranteed by applicant.

RECEIVED

SEP 21 1949 9-21-49

STATE CORPORATION COMMISSION

Applicant's Acting Agent

PLUGGING
FILE SEC 34 TWP 7 R (E)
BOOK PAGE 115 LINE 10

Date September 13, 1949

15-163-00216-00-00

HARDMAN # 1

Fink & Peterson
Contractor: Stearns Petroleum, Inc.
Commenced: August 26, 1949
Completed:

NW NE NE, Section 34, T7, R 16
Rooks County, Kansas
Elevation: 1880 D. F.

Casing Record: 8-5/8" - 225' cmtd w/135 sacks.

Tops:

Anhydrite - 1208'-1245'
Kansas City - 3029'-3275'
Arbuckle lime - 3499'-3515'

WELL LOG

	<u>From</u>	<u>To</u>
Surface clay	0	8
Rock and clay	8	90
Blue Shale	90	220
Lime	220	228
Shale	228	340
Shale, shells and iron	340	520
Sand	520	705
Red bed	705	1208
Anhydrite line	1208	1245
Shale and shells	1245	1400
Red bed	1400	1450
Shale	1450	1625
Shale and salt	1625	1690
Shale and lime	1690	2195
Lime	2195	2215
Shale	2215	2720
Lime and shale	2720	2890
Lime	2890	3275
Top of Kansas City	3029	
Shale	3275	3289
Chert	3289	3297
Lime	3297	3475
Conglomerate	3475	3499
Arbuckle lime	3499	3515

Totco

0°	200'
30 min.	685'
1°	1135'
1°	1780'
1°	2030'
1° 30 min.	2398'
1° 15 min.	2458'
1° 10 min.	2488'
1°	2723'
1°	2783'
1° 45 min.	2884'
0°	3162'

9-21-49

STATE OF KANSAS)
(SS
COUNTY OF ROOKS)

PLUGGING
FILE NO. 34-7-160
BOOK PAGE 115 LINE 10

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

SUBSCRIBED and sworn to before me this 13th day of September 1949

[Signature]

Notary Public

My Commission expires: August 17-1950



15-163-00216-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

IN REPLY PLEASE
REFER TO THIS
SUBJECT

September 20, 1949

Well No.	1
Lease	Hardman
Description	NW NE NE 34-7-16W
County	Russell
File No.	115-10

Stearns Drilling Co.
Box 313
Russell, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact District Plugging Supervisor, Mr. Elton Petty, Box 326, Hays, Kas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR