

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15 - 163 - 21,961-00-00 (of this well)  
Lease Owner Thornton E. Anderson  
Address 840 First National Bank Bldg., Wichita, Kansas 67202  
Lease (Farm Name) Jones Well No. "B" 1  
Well Location 50'N 125'W SE NE NE Sec. 29 Twp. 7 Rge. (E) 16 (W)  
County Rooks Total Depth 3352 Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log attached with this application as required yes  
Date and hour plugging is desired to begin March 4, 1983

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Leon Sohm Address Olmitz, Kansas 67564

Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Box 31, Russell, Kansas

Invoice covering assessment for plugging this well should be sent to:

Name Thornton E. Anderson

Address 840 First National Bank Bldg., Wichita, Kansas

~~and payment will be guaranteed by applicant or acting agent.~~

RECEIVED  
STATE CORPORATION COMMISSION

3-11-83  
MAR 11 1983

CONSERVATION DIVISION  
Wichita, Kansas

Signed: Mallard Drilling Co., Inc.  
By: [Signature]  
~~Applicant or Acting Agent~~

Contractor

Date: March 4, 1983

15-163-21961-00-00

D R I L L E R S L O G

COMPANY: THORNTON E. ANDERSON  
 CONTRACTOR: MALLARD DRILLING CO., INC.  
 405 Century Plaza  
 Wichita, Kansas 67202

WELL NAME: JONES "B" 1  
 DESCRIPTION:  
 50' N 125' W SE NE NE  
 Sec. 29-T7S-R16W

RIG NO.: 1

COUNTY: Rooks

TOTAL DEPTH: 3352'

ELEVATION:

COMMENCED: February 25, 1983

COMPLETED: March 4, 1983

CASING RECORD:

26 joints 8 5/8" 24# surface

D. & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, sand	0	764	Ran 1088' new 8 5/8" 24# surface casing, set and cemented at 1096' with 450 sacks 60/40 pozmix, 2% gel, 3% CaCl. Cement circulated. Plug down at 5:15 a.m., February 26, 1983.  Ran 3 drillstem tests  Ran 1 electric log  Hole plugged with 50/50 pozmix, 4% gel, as follows: 20 sacks @ 3352', 20 sacks @ 1112 feet, 100 sacks @ 800 feet, 40 sacks @ 250 feet, 10 sacks @ 40 feet, 10 sacks in rathole, 10 sacks in mousehole. Plugging completed 9:30 A.M., March 4, 1983.
Shale	764	1079	
Anhydrite	1079	1099	
Shale	1099	1930	
Shale and lime	1930	2602	
Lime	2602	2828	
Lime and shale	2828	2840	
Lime w/clay streaks	2840	2915	
Lime	2915	3352	

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF SEDGWICK )

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the Jones "B" 1 well, to the best of my knowledge.

*John Jay Darrah, Jr.*  
 John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 4th day of March, 1983.

*Dianne R. Fowler*  
 Dianne R. Fowler, Notary Public

My Commission Expires:  
 August 25, 1984

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 11 1983

CONSERVATION DIVISION  
 Wichita, Kansas