

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-193-20319-0000

API NUMBER _____

LEASE NAME Miller

WELL NUMBER B-2

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 13 TWP. 6S RGE. 36 (E) or (W)

COUNTY Thomas

Date Well Completed 11-8-84

Plugging Commenced 4-24-97

Plugging Completed 4-24-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR John J. DARRAH Jr

ADDRESS 225 N. Market, #300, Wichita, KS

PHONE#(316) 262-2249 OPERATORS LICENSE NO. 5088

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-23-97 (date)

by Carl Goodrow and Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation MARMATON Depth to Top 4521 Bottom 4525 T.D. 4862

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>MARMATON</u>	<u>chert</u>	<u>0</u>	<u>432</u>	<u>8 5/8</u>	<u>432</u>	<u>0</u>
		<u>0</u>	<u>4862</u>	<u>5 1/2</u>	<u>4862</u>	<u>0</u>

7-23-97
 RECEIVED
 APR 23 1997
 KANSAS
 STATE CORPORATION COMMISSION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Mixed 50 SAX 60/40 P02 10% gel w/ 150# balls, followed w/ 18 SAX gel, then 180 SAX w/ 200# balls,
max pressure 500#, shut in 100#. Pump down backside w/ 50 SAX w/ 100# balls,
max pressure 500#, shut in 300#. JOB complete.
Well casing perforated @ 3000' and @ 2125' on 4-23-97 by ELLI Wierlich.

Name of Plugging Contractor Allied Cementing License No. ?

Address OAKLEY, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John Jay Darrah, Jr.

STATE OF _____ COUNTY OF _____, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Philip H. Mast

(Address) Ellis, Kansas

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 97

Susan Utterback
 Notary Public

My Commission Expires: 9/2/98

