

13-193-20022-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Thomas County. Sec. 35 Twp. 6S Rge. (E)36 (W)

Location as "NE/CNW&SW&" or footage from lines C SE NE

Lease Owner Graves Drilling Co., Inc.

Lease Name Roulier Well No. 1

Office Address 505 Union Center Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Sept. 15, 19.69

Application for plugging filed (letter 9/23/69) Sept. 15, 19.69

Application for plugging approved Sept. 15, 19.69

Plugging commenced Sept. 15, 19.69

Plugging completed Sept. 16, 19.69

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 4932 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	320'	8-5/8"	320'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 1900 feet. Set first plug @ 1900 feet with 100 sacks cement. Filled hole with heavy mud to 330 feet. Set second plug with 20 sacks cement. Filled hole with heavy mud to 40 feet. Set third plug with 10 sacks cement. Used Halliburton pump truck. Pumped cement through drill pipe. Job complete @ 12:15 AM 9/16/69.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Place - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
830 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of September, 19 69



Barbara J. Layton
Barbara J. Layton Notary Public.

15-193-20022-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

ROULIER #1
C SE NE Section 35-6S-36W
Thomas County, Kansas

Commenced: August 30, 1969
Completed: September 15, 1969

OPERATOR - Graves Drilling Co., Inc.

DEPTH	FORMATION	REMARKS
From To		
0 40	Surface clay and sand	
40 322	Sand and shale	Ran 9 joints of 8-5/8" casing, set @ 320' w/300 sacks cement.
322 1755	Shale and sand	
1755 2111	Shale	
2111 2780	Shale and lime	
2780 2868	Shale	
2868 2906	Anhydrite	
2906 2943	Shale	
2943 4175	Shale and lime	
4175 4226	Lime	
4226 4595	Lime and shale	
4595 4805	Lime	
4805 4837	Lime and shale	
4837 4845	Lime, chert and shale	
4845 4881	Lime	
4881 4916	Lime and chert	
4916 4932	Lime	
4932 TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1969
CONSERVATION DIVISION
Wichita, Kansas
9-24-69

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE NE Section 35-6S-36W, Thomas County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 23 day of September, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

