

15-163-00240-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

ROOKS

County. Sec. 13 Twp. 7 Rge. (E) 20 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE $\frac{1}{4}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner. ALADDIN PETROLEUM CORPORATION

Lease Name. CAHILL Well No. 1

Office Address. 809 PETROLEUM BUILDING, WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole). DRY HOLE

Date well completed. JUNE 1 19 49

Application for plugging filed. JUNE 2 19 49

Application for plugging approved. JUNE 2 19 49

Plugging commenced. JULY 6 19 49

Plugging completed. JULY 15 19 49

Reason for abandonment of well or producing formation. NO SHOWS

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? YES

Name of Conservation Agent who supervised plugging of this well. C. D. STOUGH, GREAT BEND, KS.

Producing formation. Depth to top. Bottom. Total Depth of Well. 3544 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	180	NONE
				5-1/2	3515	1512

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH SAND 3544 TO 3505 FT.
 CEMENT 6 SAX 3505 TO 3480
 FILLED WITH MUD 3480 TO 180
 ROCK BRIDGE 180 TO 170
 CEMENT 15 SAX 170 TO 125
 MUD 125 TO 35
 ROCK BRIDGE 35 TO 30
 CEMENT 10 SAX 30 TO CELLAR

RECEIVED
 Conservation Div
 JUL 28 1949
 JUL 28 1949
 STATE CORPORATION
 COMMISSION
 KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. ALADDIN PETROLEUM CORPORATION
Address. 809 PETROLEUM BUILDING
WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

809 PETROLEUM BUILDING
(Address)

SUBSCRIBED AND SWORN to before me this 27TH day of JULY, 1949

My commission expires. April 23, 1952 [Signature] Notary Public.

22-2625 2-48-15M

PLUGGING
 FILE SEC 13 T 7 R 200
 PAGE 105 LINE 33