


15-193-20134-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Thomas County, Sec. 30 Twp. 6 Rge. 36 XE/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C NE SW
Lease Owner Dreiling Oil, Inc. & John J. Jennings
Lease Name Bear Well No. 1
Office Address Rt. #1, Victoria, KS 67671
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Date Well completed 5-31 1977
Application for plugging filed 5-31 1977
Application for plugging approved 5-31 1977
Plugging commenced 5-31 1977
Plugging completed 5-31 1977
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4968'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		0'	366'	8 5/8"	366'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set @ 1600' w. 70 sacks cement
2nd plug was set @ 300' w/20 sacks cement
3rd plug was set @ 40' w/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 08 1977
CONSERVATION DIVISION
Wichita, Kansas

0-8-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.
I, Joseph A. Hess, Sec. Treas of Drlg. Contrc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph A. Hess
JOSEPH A. HESS, HAYS, KS 67601
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of June, 19 77

My commission expires November 17, 1980.
Cecilia Basgall Notary Public.

CECILIA BASGALL
NOTARY PUBLIC
Ellis County, Kansas

DREILING OIL, INC.

Victoria, Kansas 67671

15-193-20134-00-00

Dreiling Oil, Inc. & John J. Jennings
Rt. #1
Victoria, KS 67671

WELL LOG

Company			Sec. 30	Twp. 6	Rng. 36
Farm	Bear	No. 1	Location	C NE SW	
Total Depth	4,968'		County	Thomas	
Comm.	5-20-77	Comp. 5-31-77	Elevation:	3423	K. B.
Contractor	Dreiling Oil, Inc.			3420	D. F.
	Rt. #1			3418	G. R.
	Victoria, KS 67671				

Casing Record
366' → 8 5/8"

Cement Record
250 sacks cement

Production:
D & A

Figures Indicate Bottom of Formations

0'	290'	Top Soil & Sand
290'	2638'	Shale
2638'	2880'	Shale & Hard Sand
2880'	3073'	Shale
3073'	3120'	Anhydrite
3120'	3180'	Shale
3180'	3425'	Shale - Lime Streaks
3425'	3777'	Lime
3777'	3908'	Shale & Lime
3908'	4023'	Lime & Shale
4023'	4968'	Lime
4968'	T.D.	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Bear #1.

Joseph A. Hess
JOSEPH A. HESS

Subscribed and sworn to before me this 7th day of June, 1977.

CECILIA BASGALL
NOTARY PUBLIC
Ellis County, Kansas

Cecilia Basgall
Cecilia Basgall Notary Public

My appointment expires: November 17, 1980.

JUN 08 1977
6-8-77