

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,323-00-00

LEASE NAME CHRISTIANSEN

WELL NUMBER 1

SPOT LOCATION C SW SE

SEC. 12 TWP. 6S RGE. 36W (W)

COUNTY Thomas

Date Well Completed 10/17/84

Plugging Commenced 10/17/84

Plugging Completed 10/17/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Private Oil Industries, Inc.

ADDRESS 412 Hilton Office Bldg. 1515 Cleveland Place
Denver, Colorado 80202

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing formation None Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota	water	NA	NA	8 5/8"	426'	None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug down @ 7:30pm with: 30 sacks @ 3000'
100 sacks @ 1000' (2 sacks Flocele)
50 sacks @ 450'
10 sacks @ 40'
10 sacks in Rathole, 10 sacks in Mousehole.

(If additional description is necessary, use BACK of this form.)
(210 totals sacks of cement: 50/50 Pozmix)

Name of Plugging Contractor Mohawk Drilling, Inc. License No. 6394
Address P.O. Box 1362, Great Bend, Kansas 67530


STATE OF Kansas COUNTY OF Barton, ss.

Brent B. Reinhardt (employee of operator) or
(~~XXXXXX~~) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well is filed that the same are true and
correct, so help me God.

(Signature) Brent B Reinhardt

(Address) P.O. Drawer 1367
Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 9 day of Oct, 1984



NOV 15 1984
11-15-84
RECEIVED
CONSERVATION DIVISION
Wichita, Kansas

Jeri Pebley
Notary Public

My Commission expires: 6-9-86

15-193-20323-00-00

DRILLERS' WELL LOG

DATE COMMENCED: 10-10-84
DATE COMPLETED: 10-17-84

PRIVATE OIL INDUSTRIES, INC.

CHRISTIENSEN #1

Elevation: GL-3348 DF-3355 KB-3358

C SW SE Sec. 12-6S-36W
Thomas County, Kansas

Surface Pipe: Ran 10 joints of New 8 5/8" casing, set @ 426' w/300 sacks 60/40 pozmix, 3% cc., cement did circulate.

Plugging Information: Plugged down @ 7:30 pm. w/ 30 sacks @ 3000', 100 sacks @ 1000' w/ 2 sacks Flocele, 50 sacks @ 450', 10 sacks @ 40', 10 sacks @ Rathole, 10 sacks @ Mousehole. Total cement- 210 sacks of 50/50 poxmix.

- 0 - 2984' Sand & Clay
- 2984 - 3022' Anhydrite
- 3022 - 3730' Shale & Lime
- 3730 - 4500' Lime & Shale
- 4500 - 4740' Sand & Shale
- 4740 - 4780' Conglomerate
- 4780' TD - Dry & Abandoned

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON ss.

Terry Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Terry L. Williamson
Terry Williamson

Subscribed and Sworn to before me this 19th day of October, 1984.

My Commission Expires:

7-12-87

Dianne K. Wells
Notary Public Dianne K. Wells



RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1984

CONSERVATION DIVISION
Wichita, Kansas