

Corp Comm

15-181-05053-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Sherman County, Sec. 3 Twp. 6S Rge. 37W (E) (W)

Location as "NE/CNW/SW" or footage from lines 1982 FE 1980 FSL
Lease Owner Phillips Petroleum Company
Lease Name Hartley-A Well No. 4
Office Address Box 287, Gt. Bend, Kan
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed August 1959 19
Application for plugging filed 12-23-66 19
Application for plugging approved 12-27-66 19
Plugging commenced 2-14-67 19
Plugging completed 2-15-67 19
Reason for abandonment of well or producing formation unprofitable

NORTH

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production January 1967 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well WL Nichols, PO Box 157, Morland, Kansas 67650
Producing formation Ilanos Cherokee Depth to top Bottom Total Depth of Well 4935 Feet
Show depth and thickness of all water, oil and gas formations. PTD 4796

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8	378	none
				7"	4861	3097

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 4760, dumped 5 sx cement to 4725, worked csg shot at 3090.
Recovered 3097'. Ran bailer to 3100', 10' rock bridge 398 to 388', spotted 3 yards ready mix cement 388 to 280', mudded hole to 50', 1 yard cement to 50' to surface.
Well P&A 5 p.m. 2-15-67.

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1967
CONSERVATION DIVISION
Wichita, Kansas

2-23-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Unit
Address Chase, Kan

STATE OF ~~MAKA~~ Kansas, COUNTY OF Barton, ss.
AT Slagle, Dist. Supt. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) AT Slagle
Box 287, Gt. Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of February, 19 67

My commission expires 10-27-69

Notary Public.

15-181-05053-00-00

EXPLORATION RECORD

Lease Hartley-A

Well 4

Formation Name	Top	Base	Remarks
Surface sand and clay	0	503	
Shale	503	1170	
Shale and shells	1170	2160	
Shale and shells sand	2160	2600	
Shale and shells	2600	2725	
Shale	2725	2890	
Shale and shells	2890	3045	
Shale and lime	3045	3230	
Shale and shells	3230	3425	
Lime and shale	3425	3720	
Lime	3720	4410	
Lime and chert	4410	4440	
Lime	4440	4815	
Lime and shale	4815	4900	
Lime	4900	4935	

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1967
2-23-67
CONSERVATION DIVISION
Wichita, Kansas