

15-181-00013-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Shegman County. Sec. 3 Twp. 6S Rge. 37W ~~38W~~ KW
Location as "NE/CNWxSWx" or footage from lines 660' fm/SL & 1980' fm/EL SE/4
Lease Owner Phillips Petroleum Company
Lease Name Hartley "A" Well No. 1
Office Address Box 287 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed August 16, 19 58
Application for plugging filed April 15, 19 66
Application for plugging approved April 18, 19 66
Plugging commenced April 24, 19 66
Plugging completed April 25, 19 66
Reason for abandonment of well or producing formation Depleted oil well

If a producing well is abandoned, date of last production February 23 19 66
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Cherokee, LKC & Marmaton Depth to top 4258 Bottom 4538 Total Depth of Well 4547 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	380	-
				7"	5206'	-
				4-1/2"	4348.60	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pmpd in 75 sx Jel followed by 40 sx cement by HOWCO, to bottom of cellar, filled to surface with dirt.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1966

CONSERVATION DIVISION
Wichita, Kansas

4-28-66

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing Co.
Address Hill City, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
A. T. Slagle (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. T. Slagle
Box 287, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 66

Lura Lee Parks
Notary Public.

My commission expires 10-27-69

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15-181-00013-00-00

Company: PHILLIPS PETROLEUM COMPANY
Farm: Hartley "A" No. 1

SEC. 3 T. 6 R. 37W
C SW SE

Total Depth. 5352' PB 4705'
Comm. 6-13-58 Comp. 7-9-58
Shot or Treated.
Contractor. John O. Farmer, Inc.
Issued. 11-8-58

County Sherman
KANSAS



CASING:

9 5/8" @ 380' cem. w/330 sx.
7" @ 5206' cem. w/190 sx.

Elevation. 3415' DE

Production. 345 BOPD, No wtr.
in Marmaton.

Figures Indicate Bottom of Formations.

surface	190
shale, sand & shale	440
shale	2235
shale & sand	2420
shale & shells	3080
Anhydrite	3110
shale & shells	3370
shale & lime	3720
lime	3835
lime & shale	3955
lime	4770
lime & sand	4779
lime	4803
shale	4813
lime & shale	4895
lime	4917
Mississippi	4995
Miss. & chert	5077
Mississippi	5083
Chert	5099
Chert & lime	5133
lime	5265
Arbuckle	5315
Arbuckle & sand	5346
Granite	5352
TOTAL DEPTH	

<u>SAMPLE TOPS:</u>	
Howard	4035
Topeka	4059
Heebner	4201
Toronto	4237
L/ K.C.	4253
Drum	4391
Base/K.C.	4535
Marmaton	4546
Cherokee	4686
St. Louis	4903
Spurgeon	4917
Gilc	5110
Arbuckle	5199
Reagan	5286
Weathered Granite	5332
Fresh Granite	5346

Marm perfs:	4664-70
	4633-40
	4585-88
L/KC Perfs:	4504-09
	4439-51
	4425-30
	4344-49

Plugged Back Total Depth 4705'

Producing formation penetrated at 5352'.

TOPS: SCHLUMBERGER	
Anhydrite	3080
Howard	4038
Topeka	4062
Heebner	4204
Toronto	4241
L/K.C.	4258
Drum	4396
Base/K.C.	4538
Marmaton	4550
Cherokee	4691
Mississippi (St.Louis)	4905
Spurgeon	4920
Arbuckle	5202
Reagan	5264
Pre-Cambrian (Schist)	5322
Weathered Granite	5338
Fresh Granite	5352

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1954
CONSERVATION DIVISION
Wichita, Kansas

15-181-00013-00-00

3-6-37W
Sherman County

EXPLORATION RECORD

Lease Hartley "A"

Well 1

Formation Name	Top	Base	Remarks
Surface	0	190	
Shale, sand and Shale	190	440	
Shale	440	2235	
Shale and sand	2235	2420	
Shale and shells	2420	3080	
Anhydrite	3080	3110	
Shale and shells	3110	3370	
Shale and lime	3370	3720	
Lime	3720	3835	
Lime and shale	3835	3955	
Lime	3955	4770	
		PBTD 4547'	

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1966

CONSERVATION DIVISION
Wichita, Kansas

428-66