

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

#4 API NUMBER 15-181-20,087-0000

LEASE NAME Jarvis Stivers

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #1

4620 Ft. from S Section Line

660 Ft. from E Section Line  
 C NE NE

SEC. 2 TWP. 6 RGE. 37W (E) or (W)

COUNTY Sherman

Date Well Completed \_\_\_\_\_

Plugging Commenced 6-21-93

Plugging Completed 6-23-93

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, Ks. 67202

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4960'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	410'	none
				4-1/2"	4960'	1800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plugged off bottom with sand to 4420' and 4 sacks cement. Shot pipe @ 3125', 2190', pumped 85 sacks cement & displaced to 1850', shot @ 1800', pulled 5 joints and pumped 85 sks. cement. Pulled to 300' and circulated cement to surface, pulled rest of pipe and topped off with 20 sks. cement, 65/35 pos, 10% gel. Plugging Complete.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of June

Irene Herzberg  
 Notary Public

My Commission Expires: \_\_\_\_\_

