

**AFFIDAVIT OF COMPLETION FORM**

ACO-1


This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: (Oil), gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. X Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR LIBERTY ENTERPRISES, INC.  
 ADDRESS 308 West Mill  
Plainville, Kansas 67663  
 \*\*CONTACT PERSON Charles G. Comeau  
 PHONE 913-434-4686  
 PURCHASER CRA, Inc.  
 ADDRESS P.O. Box 7305  
Kansas City, Missouri  
 DRILLING CONTRACTOR PIONEER DRILLING COMPANY  
 ADDRESS 308 West Mill  
Plainville, Kansas 67663

API NO. 15-163-21,491-00-00  
 COUNTY Rooks  
 FIELD Riffe Extension  
 PROD. FORMATION Arbuckle  
 LEASE Kriley  
 WELL NO. #1  
 WELL LOCATION NW NW SE  
2310 Ft. from South Line and  
2310 Ft. from East Line of  
 the SE/4 SEC. 20 TWP. 7S RGE. 17W

PLUGGING CONTRACTOR ADDRESS \_\_\_\_\_

TOTAL DEPTH 3350' PBTD \_\_\_\_\_  
 SPUD DATE 11-15-81 DATE COMPLETED 12-11-81  
 ELEV: GR 1753' DF 1756' KB 1758'



**WELL PLAT**  
 KCC   
 KGS   
 MISC   
 (Office Use)

DRILLED WITH (~~XXXXX~~) (ROTARY) (~~XXXX~~) TOOLS (New) / (~~XXXX~~) casing.  
**CASING RECORD**

**Report of all strings set— surface, intermediate, production, etc.**

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	1187'	common	450	3%cc, 2% gel
Production	7 7/8"	5 1/2"	14#	3345'	A.S.C.	150	RECEIVED STATE CORPORATION COMMISSION JAN - 5 1982

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4 per ft.		3273-78
TUBING RECORD					
Size	Setting depth	Packer set at			
2 7/8	3320'				

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Natural	RECEIVED STATE CORPORATION COMMISSION DEC 30 1981 12-30-81 CONSERVATION DIVISION

Date of first production 12/11/81 Producing method (flowing, pumping, gas lift, etc.) pumping unit Gravity Wichita Kansas  
 RATE OF PRODUCTION PER 24 HOURS Oil 20 bbls. Gas \_\_\_\_\_ MCF Water % bbls. Gas-oil ratio \_\_\_\_\_ CFPB  
 Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Perforations \_\_\_\_\_

\*\*The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum \_\_\_\_\_ DEPTH 255'

Estimated height of cement behind Surface Pipe \_\_\_\_\_.

DV USED? None


**WELL LOG**

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
shales	0'	216'		
sand & shale & pyrite	216'	395'		
	395'	1075'		
shales and sands	1075'	1177'		
shale and sand	1177'	1187'		
anhydrite	1187'	1208'		
shales	1208'	1550'		
shale and limes	1550'	1955'		
limes and shales	1955'	2060'		
shale and lime	2060'	2142'		
lime and shale	2142'	2450'		
lime and shales	2450'	2688'	Topeka	2681''
lime and shale	2688'	2840'		
lime and shale	2840'	2967'	Heebner	2892'
lime and shales	2967'	3050'	Toronto	2915'
lime and shale	3050'	3081'	Lansing	2936'
lime and shale	3081'	3125'		
lime and shale	3125'	3170'	Base	3167'
lime and shale	3170'	3195'		
lime and shale	3195'	3240'		
lime and shale	3240'	3350'	Arbuckle	3270'
	3350'	RTD		

**A F F I D A V I T**

STATE OF KANSAS, COUNTY OF ROOKS SS, \_\_\_\_\_

Charles G. Comeau OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES THAT HE IS Secretary-Treasurer (FOR)(OF) LIBERTY ENTERPRISES, INC. OPERATOR OF THE Kriley LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 11th DAY OF December, 1981, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT. FURTHER AFFIANT SAITH NOT.

(S)   
Charles G. Comeau

SUBSCRIBED AND SWORN BEFORE ME THIS 29<sup>th</sup> DAY OF December 1981

SHARON GARVERT  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Expires 10/24/84

MY COMMISSION EXPIRES: \_\_\_\_\_

Sharon Garvert  
NOTARY PUBLIC  
Sharon Garvert