

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
FEB - 3 1981
2-2-81
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 163 - 21,209 - 0000 (of this well)
Lease Owner F & M Oil Company
Address 422 Union Center, Wichita, KS 67202
Lease (Farm Name) K. U. ENDOWMENT Well No. #2
Well Location S/2 SE NW Sec. 30 Twp. 7S Rge. 17W (E) (W) 17W
County Rooks Total Depth 3387' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 12:30 p.m., 1/17/81

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig (Toolpusher) Address 702 S. 2nd Street, Hill City, KS 67642

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, KS 67202

Invoice covering assessment for plugging this well should be sent to:

Name F & M Oil Company

Address 422 Union Center, Wichita, KS 67202

and payment will be guaranteed by applicant or acting agent.

Signed: 
Applicant or Acting Agent

Jack L. Partridge, Asst. Sec./Treas.
Date: January 27, 1981

CONTRACTOR'S WELL LOG

15-163-21209-00-00

OPERATOR: F & M Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: K. U. ENDOWMENT #2
 LOCATION: S/2 SE NW, Section 30-7S-17W
 Rooks County, Kansas
 SPUD DATE: 1/09/81
 COMPLETION DATE: 1/17/81

0	200	Shale & Sand
200	780	Shale
780	1240	Shale & Sand
1240	1257	Anhydrite
1257	1291	Shale & Sand
1291	1316	Anhydrite
1316	1818	Shale
1818	3025	Lime & Shale
3025	3135	Lime
3135	3205	Lime & Chert
3205	3209	Lime
3209	3330	Lime & Shale
3330	3350	Dolomite & Arbuckle
3350	3355	Lime
3355	3387	Arbuckle
	3387	Rotary Total Depth

Spud hole @ 1:30 a.m., 1/09/81. Drilled 1259' of a 12 1/4" hole. Ran 31 jts. of new 8 5/8" 24# casing (tally 1253.45 overall) Set @ 1254' with 550 sx. of common cement, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 9:00 a.m., 1/10/81.

RTD @ 3387'. LTD @ 3388'. Going in the hole to plug plugging orders. Set 1st Plug @ 1200' with 60 sx. Set 2nd Plug @ 330' with 30 sx., Set 3rd Plug @ 40' Solid Bridge with 10 sx., Rathole with 5 sx. 50-50 posmix, 6% gel. State Plugger - Marion Schmidt. Cement by Sun Cement. Plug was down @ 12:30 p.m., 1/17/81.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

REC - 21981
 2-2-81
 CONSERVATION DIVISION
 Kansas, Kansas


Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the K. U. ENDOWMENT #2, S/2 SE NW, Section 30-7S-17W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec./Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 27th day of January, 1981.

Jeanette A. Metheny
 Jeanette A. Metheny, Notary Public



State of Kansas



15-163-21209-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Bldg.
WICHITA, KANSAS 67202

February 18, 1981

WELL PLUGGING AUTHORITY

Well No.	2
Lease	K. U. Endowment
Description	S $\frac{1}{2}$ SE NW
Section	30-7S-7W
County	Rooks
Total Depth	3387'
Plugging Contractor	Abercrombie Drlg., Inc.

F & M. Oil Co.,
422 Union Center
Wichita, Ks. 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,


For Administrator

Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, Kansas, 67601

is hereby assigned to supervise the plugging of the above named well.