

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 077-20728-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: EDMISTON OIL COMPANY INC KCC License #: 5042

Address: 125 N MARKET SUITE 1130 City: WICHITA

State: KS Zip Code: 67202 Contact Phone: (316) 265 - 5241

Lease: GREEN Well #: 4 Sec. 22 Twp. 31 S. R. 9 East West

SE - NE - NE Spot Location / QQQQ County: HARPER

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8.625 Set at: 312 Cemented with: 270 Sacks

Production Casing Size: 4.500 Set at: 4490 Cemented with: 220 Sacks

List (ALL) Perforations and Bridgeplug Sets: Pf 4436-44, 3 spf, MISSISSIPPI

Elevation: 1636 (G.L. / K.B.) T.D.: 4490 P.B.T.D.: 4488 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): PULL CASING, SET PLUGS AS DIRECTED BY FIELD STAFF

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

SEP 19 2005

If not explain why? _____

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: DALE MAY, SUPERINTENDENT

Phone: (620) 792 - 6924

Address: P O BOX 232 City / State: GREAT BEND, KS 67530

Plugging Contractor: EXPRESS WELL SERVICE KCC License #: 6426

Address: P O BOX 19 VICTORIA KS 67671 Phone: (785) 735 - 9405

Proposed Date and Hour of Plugging (if known?): WEEK OF SEPT 19TH, WILL CALL

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent.

Date: 9/19/2005 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEP 19 2005

CONSERVATION DIVISION
WICHITA, KS

TYPE AFFIDAVIT OF COMPLETION FORM ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5041 EXPIRATION DATE 6/30/83

OPERATOR Ram Petroleum Corporation API NO. 15-077-20,728

ADDRESS 1260 KSB&T Bldg. COUNTY Harper

Wichita, Kansas 67202 FIELD Spivey-Grabs Basil

** CONTACT PERSON Robt K. Edmiston PROD. FORMATION Mississippi
PHONE (316) 265-5241

PURCHASER (oil) Koch (gas) KS Gas Supply LEASE GREEN

ADDRESS P.O. Box 2256 Box 300 WELL NO. 4

Wichita, KS 67201 Tulsa, OK 74102 WELL LOCATION SE NE NE

DRILLING Graves Drilling Co., Inc. 990 Ft. from North Line and

CONTRACTOR 330 Ft. from East Line of

ADDRESS 910 Union Center Bldg. the NE (Qtr.) SEC 22 TWP 31S RGE 9W.

Wichita, Kansas

PLUGGING CONTRACTOR WELL PLAT (Office Use Only)

ADDRESS

	22		

KCC
KGS
SWD/REP
PLG.

TOTAL DEPTH 4490' PBSD 4488'

SPUD DATE 10/19/81 DATE COMPLETED 12/21/81

ELEV: GR 1625 DF KB 1636

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 312 DV Tool Used? no

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Robt K. Edmiston, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Robt K. Edmiston
(Name) Robt K. Edmiston

SUBSCRIBED AND SWORN TO BEFORE ME this 5th day of August, 19 82.



Marilyn E. Fox
(NOTARY PUBLIC) Marilyn E. Fox

MY COMMISSION EXPIRES: November 14, 1985

** The person who can be reached by phone regarding any questions concerning this ation.

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Ram Petroleum Corporation LEASE Green #4

SEC. 22 TWP. 31 SRGE. 9W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Redbed and Sand	0	312		
Redbed and Shale	312	1358		
Shale	1358	1963		
Shale and Lime	1963	4490	Lansing	3686(-2050)
			Base/KC	4215(-2579)
			Cherokee Shale	4346(-2710)
			Mississippi	4416(-2780)
RTD	4490		LTD (Electra-Log Logged)	4493(-2857)
<p>Drill Stem Test #1, 4414-4445 (Mississippi) 30-30-120-30. Strong blow on 1st opening. Strong decreasing at end of second opening. Rec. 1280' gas in pipe & 140' slightly oil spotted mud. ISIP 537#; FSIP 475#; IFP 31-30#; FFP 31-50#.</p> <p>Drill Stem Test #2, 4445-4460 (Mississippi) 30-30-120-30. Strong blow on first and second opening. Gas to surface/60 min. - ga. 1350 cfg/d. Rec. 285' of fluid (105' oil and water cut gassy mud & 180' slightly oil cut water). ISIP 982#; FSIP 897#; IFP 61-71#; FFP 71-122#.</p>				

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface casing	12 1/4"	8-5/8"	24	312	common	270	2% gel, 3% cc
Production pipe	7-7/8"	4 1/2"	10.5	4488	50/50 posmix	220	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3		4436-4444

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acid: 300 gal, 15% demud	4436-4444
Frac: 11,000# 20-40 sd	" "

Date of first production 12/23/81	Producing method (flowing, pumping, gas lift, etc.) pumping	Gravity 29.8
--------------------------------------	--	-----------------

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	%	Gas-oil ratio
	bbls.	bbls.	MCF		

Disposition of gas (vented, used on lease or sold) sold	Perforations
--	--------------

* NOTE: Edmiston Oil Company, Inc., operates this well from the casing point.

SEP 19 2005

R O T A R Y D R I L L E R S ' L O G

CONSERVATION DIVISION
WICHITA, KS

OPERATOR: Ram Petroleum Corporation DRILLING COMMENCED: October 19, 1981
800 Vickers-KSB&T Building
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: October 27, 1981
910 Union Center
Wichita, Kansas 67202

CASING RECORD: 10 Jts. 312' of used 8-5/8" LOCATION: Green No. 4
cemented with 270 sacks SE NE NE
110 Jts. 4488' of new 4 1/2" Section 22-31S-9W
cemented with 220 sacks Harper County, Kansas

0 - 312 Red bed & sand
312 - 1358 Red bed & shale
1358 - 1963 Shale
1963 - 4490 Shale & lime
4490 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

Copy sent to:
State Corporation Commission
Kansas Geological Society
Kansas Geological Survey

GRAVES DRILLING CO., INC.

By Betty Brandt
Secretary-Treasurer

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 4th day of November, 1981.

Rebecca L. Matthews
Rebecca L. Matthews Notary Public

My commission expires: May 17, 1983

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Edmiston Oil Company, Inc.
125 N. Market, Ste 1130
Wichita, KS 67202-1721

September 21, 2005

Re: GREEN #4
API 15-077-20728-00-00
SENENE 22-31S-9W, 990 FNL 330 FEL
HARPER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely


David P. Williams
Production Supervisor