

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21413-00-00
Spot: ~~GNENWNE~~ NWNENE Sec/Twnshp/Rge: 30-7S-17W
4950 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: GRIFFITH Well Number: 6
County: ROOKS Total Vertical Depth: 3292 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size feet: \$106.99
Surface Casing: Size 8.625 feet: 1216 450 SX CMT
Production: Size 5.5 feet: 3251 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/19/2002 11:30 AM

Plug Co. License No.: 7076 Plug Co. Name: BLACK DIAMOND OIL, INC.

Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 22 sxs gel.
5 1/2" casing parted at 1206'. Pulled out.
CIBP at 3127'. LKC Perfs at 3050' - 3056'.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 12/19/2002 2:30 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 7/8" tubing to 3000'.
Allied pumped 15 sxs gel spacer, followed with 50 sxs 60/40 pozmix - 10% gel and 250# hulls.
Pulled tubing to 1300'.
Allied pumped 7 sxs gel spacer, followed with 40 sxs cement and 250# hulls.
Pulled tubing to 500'.
Allied pumped 150 sxs cement - cement circulated.
PTOH.
Topped off with 10 sxs cement. Hole stayed full.
Note: Top 5 1/2" casing 1206'.

RECEIVED
JAN 03 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 1-3-03

INV. NO. 2003061026

Form CP-2/3

DEC 30 2002

RIM OIL CO.
512 S. WYOMING

PLAINVILLE, KS. 67663

CONTR RANGER DRILLING CO. INC. CTY ROOKS

GEOL KENNETH VEHIGE FIELD RIFFE

E 1782 KB E 9/10/81 CARD CM ISSUED 1/21/82 IP P 60 BOPD & WTR
1777 GL ARB OH 3251-3292 $\frac{1}{2}$

API 15-163-21,413

LOG	TOPS	DEPTH	DATUM
ANH		1215	+ 567
B ANH		1252	- 530
TOP		2703	- 921
KH		2798	-1016
QH		2852	-1070
HEEB		2912	-1130
TOR		2937	-1155
LKC		2956	-1174
B KC		3183	-1401
MARM		3197	-1415
ARB		3246	-1464
RTD		3284	-1502
LTD		3292 $\frac{1}{2}$	-1510

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

REPLACEMENT CARD:

#6 GRIFFITH

30-7-17W
NE NW NE

+	+	+	+
+	+	+	+

8-5/8" 1216, 5 $\frac{1}{2}$ " 3251

NO DST'S

MICT - CO, PF (ARB OH), SWB DWN W/GSO,
NAT, POP, P 60 BOPD & WTR

CORRECTION: 3/4/82 - ORIGINALLY
FIRST REPORTED IN NW NE NE - 1ST
CORRECTION CHANGED LOC TO NE NE NE