

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21322-00-00  
Spot: CNENENW Sec/Twnshp/Rge: 30-7S-17W  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: RIFFE Well Number: 2  
County: ROOKS Total Vertical Depth: 3239 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 1143 450 SX CMT  
Production: Size 5.5 feet: 3222 150 SX CMT  
Liner: Size feet:

105.27

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/29/2001 2:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 300# hulls.  
Arbuckle O.H. 3222' - 3239'.  
LKC Perfs 2710' - 3094'.  
Sand back to 2650' w/5 sxs cement on top.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/30/2001 4:30 PM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Sanded back to 2649' with 5 sxs cement on top.  
Shot pipe off at 2025'.  
Pulld 5 1/2" casing to 1200'.  
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls.  
Pulled to 700'. Allied pumped 100 sxs - cement circulated.  
POOH.  
Topped off with 20 sxs.

RECEIVED  
SEP 11 2001  
9-11-2001  
KCC WICHITA

Remarks: 08-29-2001 - RIG BROKE DOWN, COMPLETED 08-30-2001. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

9-11-01

INV. NO.

2002060451

SEP 05 2001

RIM OIL CO  
 512 S WYOMING #2 RIFFE 30-7-17W  
 PLAINVILLE, KS 67663 NE NE NW  
 CONTR RANGER DRILG CO INC CTY ROOKS

GEOL \_\_\_\_\_ FIELD RIFFE

E 1757 KB CME 6/21/81 <sup>FARD</sup> ISSUED 1/21/82 IP P 31 BOPD & WTR  
 1752 GL LKC 2914-3094 OA  
 API 15-163-21,322

•		
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
TOP		2682	- 925
KH		2774	-1017
QH		2829	-1072
HEEB		2886	-1129
TOR		2913	-1156
LKC		2932	-1175
BKC		3158	-1401
MARM		3171	-1414
ARB		3218	-1461
RTD		3240	-1483

NO DST'S  
 MICT - CO, PF(KC) 9/3090-94, 9/3029-33,  
 9/2970-74, 7/2914-17, AC 500G (MA) &  
 500G (NEG), EA ZN, POP, P 31 BOPD & WTR  
 1/15/82

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

15-163-21,322  
 1757 KB  
 1752 GL  
 6/21/81  
 1/21/82  
 P 31 BOPD & WTR  
 LKC 2914-3094 OA