

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20763-00-00
Spot: CSEENENW Sec/Twnshp/Rge: 30-7S-17W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: RIFFE Well Number: 1
County: ROOKS Total Vertical Depth: 3297 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1171 475 SX CMT
Production: Size 4.5 feet: 3295 175 SX CMT
Liner: Size feet:

\$107.15

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/31/2001 2:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
4 1/2" at 3295'. PBSD 3288'.
Perfs 3100' - 3275'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/31/2001 3:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 3050' with 4 sxs cement on top.
Casing parted at 700'.
Allied pumped 125 sxs 60/40 pozmix - 10% gel with 500# hulls.
Pulled casing out.
Allied pumped 125 sxs.
Max. P.S.I. 800#. S.I.P. 500#.

RECEIVED
SEP 11 2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

9-11-01

INV. NO.

2002060451

SEP 05 2001

RIM OIL CO.
 512 S. WYOMING
 PLAINVILLE, KS. 67663
 CONTR JOHN O. FARMER, INC.


REPLACEMENT CARD:
 #1 RIFFE

30-7-17W
 SE NE NW

CTY ROOKS

GEOL DICK GREEN FIELD WC(RIFFE DISC)

E 1767 KB CM 4/17/78 CARD ISSUED 8/31/78 IP P 9 BOPD & NW
 1762 GL



TOR 2916-2920
 ARB 3234-3275

API 15-163-20,763

SMP	TOPS	DEPTH	DATUM
TOP		2686	- 919
HEEB		2893	-1126
TOR		2916	-1149
LANS		2937	-1170
B KC		3162	-1395
MARM SH		3172	-1405
ARB		3235	-1468
RTD		3295	-1528

8-5/8" 250/475sx, 5 1/2" 3295/175sx
 DST (1) 2711-2725/TIMES NA, REC 250'
 SW, FSIP 1030#, FP NA
 DST (2) 2839-2880/TIMES NA, REC 110'
 SW, FSIP 930#, FP NA
 DST (3) 2881-2931/TIMES NA, REC 70'
 HOCM, 60'MO, SIP 1109-1004#, FP NA
 DST (4) 2929-3000/TIMES NA, REC 305'
 SW, ISIP 908#, FP NA
 DST (5) 3021-3049/TIMES NA, REC 434'
 SW, FSIP 1137#, FP NA
 DST (6) 3075-3140/TIMES NA, REC 60'TM,
 60' SW W/OIL SPKS, FSIP 1004#, FP
 NA
 MICT - CO, PF 3272-3275, 3259-61, 3249-
 51 & 3234-38, AC 500 + 1500 REG AC,
 (OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS