

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20788-00-00  
Spot: NWSWSESE Sec/Twnshp/Rge: 23-10S-21W  
495 feet from S Section Line, 1155 feet from E Section Line  
Lease Name: BARBER Well #: 3  
County: GRAHAM Total Vertical Depth: 3747 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY, A GENERAL  
Address: 805 CODELL RD.  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3744	0	100 SX CMT
SURF	8.625	260	0	120 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2005 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LOUIS "DON" BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-7202

Proposed  
Plugging  
Method:

Ordered 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/28/2005 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

Perfed casing at 1650' and 950'.  
RIH with tubing to 1900' - spotted 110 sxs cement with 100# hulls mixed in cement.  
Pulled tubing to 700' - spotted 50 sxs cement with 100# hulls mixed in cement - cement circulated at surface.  
POOH with tubing and squeezed casing with 50 sxs cement.  
Max. P.S.I. 800#. S.I.P. 300#.  
8 5/8" surface pipe - squeezed 5 sxs cement.  
Max. P.S.I. 500#. S.I.P. 250#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

(H)

Signed

Dennis L. Hamel

(TECHNICIAN)

**INVOICED**

DATE

9.21.05

INV NO

2006060455

RECEIVED

SEP 20 2005

KCC WICHITA

Form CP-2/3

AUG 30 2005

ICER ADDIS #3 BARBER 23-10-21W  
 DRAWER 8038, WICHITA, KS. 49' FSL &  
 CONTR MURFIN DRLG. CO. CTY GRAHAM 1155' FEL, SE

GEOL DICK FOLEY FIELD COOPER

E 2152 KB C40/17/75<sup>CARD</sup> ISSUED 1/8/76 IP P 5 BOPD + 10 BOPD  
 ARB 3730-45

API 15-065-20,788

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		1616	+ 536
TOP		3177	-1025
HEEB		3384	-1232
TOP		3410	-1258
LANS		3426	-1274
BKC		3650	-1498
CONG		3710	-1558
ARB		3730	-1578
RTD		3747	-1595
LTD		3751	-1599

8 5/8" 260/150sx, 5 1/2" 3745/100sx  
 DST (1) 3731-3737/30-30-60-30, 120" SMO,  
 40' VHO CM, SIP 213-180#, FP 22-32#,  
 53-64#  
 DST (2) 3737-3742/30-30-60-30, 170" WMO,  
 SIP 245-202#, FP 21-31#, 53-74#  
 DST (3) 3741-47/30-30-60-30, 85" HMO,  
 SIP 245-202#, FP 10-21#, 32-51#  
 MICT - CO & PF 20/3740-45, A 250, 20/  
 3730-35, A 250, REC LD, POP

INDEPENDENT OIL & GAS SERVICE

0116  
 0116  
 0116